
Q1188 - 188 Balnarring Rd, Merricks North

Amanda Hagan & Kevin McCoy C/O Rod Hannah Design
Office 15, 4 High St
Hastings
VIC 3912
P: (03) 5983 1927

Quote Number: Q1188
Quote Valid for 30 days
Building Type: Single storey
Quote Date: 4/7/2026

Dear Amanda & Kevin,

Please find attached a quote from Coastal Builders for your new home at 188 Balnarring Road, Merricks North.

Below is some key information about our business to help you better understand who we are and how we work.

Coastal Builders is a residential building company proudly owned and operated by Peter and Lauren Leyden. We have been delivering high-quality construction services for over 15 years across the Mornington Peninsula and surrounding Melbourne suburbs. We have built our business on strong client relationships and a reputation for dependable, high-quality workmanship. We take pride in every project we undertake, and the trust we earn is reflected in the repeat work and referrals we continue to receive.

When you choose to work with Coastal Builders, you can expect hands-on involvement from myself throughout the duration of your project. I'm regularly on-site, working alongside our experienced team, which includes four qualified carpenters and two apprentices.

Our tradespeople have been with Coastal Builders since the beginning. They understand the high standard of workmanship we uphold and are committed to meeting your expectations for quality and finish. In most cases, some of our key trades will visit the site alongside myself during the quoting process to get a solid understanding of the scope and to flag any potential challenges early on.

We're also proud members of the Housing Industry Association (HIA), a reflection of our ongoing commitment to professional standards in the building industry.

The attached estimate has been broken down into clear categories, with detailed information included in the specifications section for your review.

If you would like to speak to any of our recent clients please feel free to contact any of the below clients for reference.

Dave Brewster - Balnarring Beach - Ph: 0409 559 905

Jesse Ransom - Mt Martha - Ph: 0437 652 213

Jonty Golshevsky - Somers - Ph: 0419 569 903

Please don't hesitate to get in touch if you have any questions or would like to discuss anything further.

Kind regards,
Peter Leyden
Coastal Builders

Specifications and Inclusions

Demolition

- **SCOPE OF WORKS** - A single-story brick veneer and timber clad house on timber and concrete floors with steel roofing and surround verandahs on concrete paving. A stand-alone timber laundry and WC building on a slab. An attached carport with steel roofing on a concrete slab. A steel shed on a concrete slab. An inground swimming pool, pool shed and all pool concrete paving. Note: a separate barn complex is not included. All concrete slabs, stumps and pads and all concrete paving, including the pool zone. Asbestos being all visible external cement sheet deemed to be asbestos sheeting for the purposes of this quote. No vegetation is included. No site earthworks/excavation/removal or supply of fill/site scrape/cut are included. Site to be track rolled & left roughly in accordance with post demolition levels (falls and rises as created by the removal of below ground structures). Includes de gassing of airconditioning units.
- **DEMOLITION SERVICES** - Demolition is by hand & excavator & rubbish removed by tipper truck. On-site management of all contractors. All necessary insurances for demolition & compliance with WorkSafe Vic. Site track rolled & left clean and tidy.
- **EXCLUSIONS** - Abolishment or redirection of services & associated costs if required. Builder and owner to organize. Asset Protection permit. Tree removal permit (required by Council).
- **ASBESTOS** - Asbestos being all visible external cement sheet deemed to be asbestos sheeting for the purposes of this quote. Includes Clearance Certificate.
- **VEGETATION REMOVAL** - No vegetation is included. No site earthworks/excavation/removal or supply of fill/site scrape/cut are included.
- **PERMITS** - Building Permit is included.
- **PRICE** - Total price for demolition services listed above is \$46,100 (incl GST).

Roofing & Cladding

- Supply and fit Colorbond 25mm rib 465mm cover snap lock to roof and walls.
- Includes proctor wrap, Colorbond ridges/barge cappings/trims, Colorbond valleys, Colorbond 200mm half round gutter, Colorbond 90mm downpipes.
- 1 x Velux CK02 skylight
- Colorbond .48 deck roof and 60mm blanket to deck roof areas with 1 degree pitch.
- Chimney flashings and ventilation.

Septic and Irrigation

- Supply and install Aqua Nova Advance Septic Treatment System.
- Supply and install 500m² subsurface irrigation assembly.
- Council application fee included.
- 1 year service.

Plumbing

- **Rough-in/Fit-Off** - Hot & Cold water supply to all required fixtures. Connection of all fixtures to sanitary drain. Installation of sanitary vents. Installation & testing of all fixtures. Installation of 500kPa pressure limiting valve @ house. Supply & installation of HWS (Stiebel Altron WWK302H). Installation of suspended drains (sewer). Installation of water supply from pump to house. Installation of external taps. Installation of vegetable garden tap. Installation of auto top-up water point in pool equipment area
- **Sewer** - Supply & install approximately 38m of 100mm Sewer drain, connecting house suspended sewer drain to waste treatment plant.
- **Gas Service** - Supply & install approximately 58m of Gas service line from service court to gas point locations in house & alfresco. Installation & testing of gas appliances.
- **Stormwater** - Supply & install approximately 210m of 100mm stormwater drain to service all house & alfresco downpipes, connected to tanks (roof water only). Supply & install dirty stormwater drain, connected to LPD at Balnarring Road approximately 300m of 100mm stormwater drain, to service all groundwater / ag drains / tank overflow. Ag drains, supply & install ag drains as per specifications behind all block / retaining walls, including around tank area at the shed, connected to dirty stormwater line. Allowance for 75m³ Scoria; but will depend on batter cuts etc. *Any extra rock to be charged at meter rate.
- **Water Tanks** - Supply & install 4x25,000L Colorbond steel rain water tanks in Monument. Supply & install of 1x 25,000L Colorbond steel rainwater tank to be provided with appropriate CFA outlet, fittings, fixtures, pipes & signage. All water tanks to be linked & balanced and connected to stormwater drain from house.
- Compliance certificate.
- Please note: Existing water pump & filter assumed to be in working order and to be re-used. Existing gas bottles to be re-used but quote includes new regulator & Gas bottle set-up.

Specifications and Inclusions

Plumbing

- Based on past experience, a basement/Garage typically has a central pump pit that everything feeds to and a two stage pump system, as specified by an engineer. This would include (but not be limited to) a main pump, a back-up pump and a high-level float alarm. An off the shelf submersible pump may not be suitable in this instance and further information should be provided.

Concrete Polishing

- Mechanically Polished Concrete finishes to two fireplace hearths one internal and one in outdoor pavilion and one pizza oven concrete plinth also in the outdoor pavilion. Works will include:
- 1st pass at 30 grit diamond grinding and vacuuming using single phase hand equipment to concrete surfaces to remove surface of existing concrete floor along with any existing contaminants and curing agents etc and to provide a clean exposed aggregate finish to existing concrete..
- 2nd and 3rd pass diamond grinding and vacuuming using single phase hand equipment to concrete surfaces to conduct Totally Restore grouting process as required to fill majority of any small holes, hairline cracks and natural porosity of concrete and to provide a clean smooth finish to concrete.
- Filling of any larger cracks or holes using Patch & Anchor repair mortar.
- Detailed grinding of repairs to provide a smooth uniform floor finish.
- Application of Totally Boost Densifier to concrete surfaces prior to each of the first of three passes of Worx Plus Specialty resin polishing pads using single phase hand equipment consisting of 50, 100 and 200 grit diamond impregnated resin pads to provide a polished finish to concrete surfaces in a satin finish.
- Final polishing and vacuuming of concrete surfaces using 400 grit tempo pads to provide a clean finish to in readiness for application of penetrating sealer.
- Application of Alchemy penetrating sealer or similar to polished concrete surfaces to provide final stain resistant finish.
- Final buffing of concrete surfaces using blue nylon pads.

Windows

- Based on quote provided by Design Window Solutions to supply and site glaze Thermally Broken windows/doors, with BAL 40 compliance, as per discussions with Mike Joseph.
- Includes fly screens with aluminum mesh for all operable windows. No screens allowed for D3 and D5.
- Please note an impending glass price increase of 4% as of September 2026. This will add approximately \$950 (ex GST).

Hydronic Heating

- Supply and install Hydronic heating system.
- Brugman Steel Panel Radiators Compact 4: Steel, gloss white, on/off valve, 25 year warranty, white pipe and cover plates.
- Includes hydronic heated towel rail. Can be powder coated.
- New Bosch 35kW high efficiency 8300 water heating unit.
- Pipework to comprise IVAR Italian Made PEX-AL-PEX pipe.
- The system will be commissioned and adjusted to ensure optimum performance. Operating instructions, maintenance instructions and the manufacturers equipment manuals will be provided to ensure an understanding of operating the system.
- Plumbing Industry Compliance Certificate.
- OPTIONAL UPGRADE - PANEL HEAT CONTROL: Thermostatic head that provides temperature control over an individual panel. Ideal for bedrooms. \$55 ex GST each.

Reverse Cycle Air Conditioning Systems

- Supply and install inverter reverse cycle air conditioning systems as follows:
- CU 1 – 1 x FUJITSU AOTH54KBTA – 13.0 kW Heat Pump (Outdoor unit). AC 1.1 (Bedrooms 2, 3,4 / MPR) – 1 x FUJITSU ARTH54KHTA – 13.0 kW High Static Ducted
- CU 2 – 1 x FUJITSU AOTH54KBTA – 13.0 kW Heat Pump (Outdoor unit). AC 2.1 (Kitchen / Dining) – 1 x FUJITSU ARTH54KHTA – 13.0 kW High Static Ducted
- CU 3 – 1 x FUJITSU ARTH24KMTAP – 7.1 kW Heat Pump (Outdoor unit). AC 3.1 (Living) – 1 x FUJITSU AOTH24KBTA – 7.1 kW Mid Static Ducted
- CU 4 – 1 x FUJITSU AOTH24KBTA3 – 6.8 kW Heat Pump (Outdoor unit). AC 4.1 (Master Bedroom) – 1 x FUJITSU ARTH12KSLAP – 3.5 kW Mini Ducted. AC 4.2 (Study) – 1 x FUJITSU ARTH09KSLAP – 2.5 kW Mini Ducted
- All supply air grilles will be Linear bar / slot type – powder coated white (Sizes TBC).
- All Thermostats will be hard wired type.

Specifications and Inclusions

Reverse Cycle Air Conditioning Systems

- Locations of all units / grilles and thermostats to be determined onsite before works commence.
- Certificates of plumbing compliance and electrical safety provided.
- 5 year manufacturer's warranty on unit. 6 years Installation warranty governed by the BPC (Building and Plumbing Commission)

Fireplace

- Supply and install of freestanding Cheminees Philippe Radiante 800 wood heater.
- Back flashing included.

Rendering

- Grey concrete effect to back wall of outdoor fireplace, Chimney & Slab Edge
- 1st coat: apply 3mm- 4mm of acrylic render to seal the surface of brickwork to be rendered.
- Grey concrete effect: Supply and install 2 x coats of Coharo grey concrete effect, each coat lightly spray fine mists of water over drying surface and polish with purpose-made trowels, this creates the desired concrete effect.
- Note: all external Corners, Sills, and Reveals are formed using aluminum straight-edges for a sharp, straight finish throughout project. Colour: TBC.

Stone Work to Fireplace Recess

- Baw Baw Walling 30-50mm thick, Split 5 sides sawn back from Eco Outdoor, as specified by Rod Hannah Design and Project 5 Interiors.
- Installation of Baw Baw Walling, grouted and utilising heat-rated glue.

Electrical

- New Dwelling -
- Pavillion: 1 x underground Power supply, 8 x gimble style down lights, 1 x w/proof power point.
- Vegetable Garden: 1 x double w/proof power point.
- Garage: 1 x chassis type NHP distribution board in storeroom including all required safety switches and circuit protection, 2 x LED strip lights, 6 x down light points, 1 x external double power points, 14 x double power points, 2 x single phase 32A car charging points connected to isolators, 1 x HWS 20A circuit connected to isolator, 1 x lift circuit 20A single phase connected to isolator, 1 x data cabinet modem location TBC.
- First Floor: 10 x double power points with integrated USB C charging points, 2 x recessed floor box power points, 68 x double power points, 4 x double w/proof power points, 4 x ceiling blind power supply, 10 x data outlets wired back to modem location, 1 x TV outlet connected to new antenna, 1 x heated towel rail, 2 x oven circuits, 1 x induction cooktop circuit with isolation switch, 1 x gas cooktop power supply, 1 x rangehood power supply, 5 x ceiling fan points, 6 x smoke detectors hard wired and interconnected, 88 x LED down light points, 5 x exhaust fans ducted to external air 14 x wall light points
- First Floor cont: 5 x sensors with override switch, 4 x step lights, 1 x fan/ heat/light tastic point, 4 x garden lights, 4 x porch light points, 4 x dimmers as per indicated locations, 3 x 3-way switches, 5 x 2-way switches, 4 x pendant light points, 1 x bathroom LED strip, 1 x bed 2 ensuite LED strip, 1 x powder room LED strip, 1 x master ensuite LED strip, 1 x study LED strip, 1 x living room LED strip, 1 x kitchen LED strip, 2 x pantry LED strip, 2 x laundry LED strip, 1 x pool sub board to nominated location
- As per the Project 5 Interiors specification, an allowance has been made for the following:
- Unios lights - 69 x Titanium G2 Downlights with flicker free driver, 4 x Apex Adjustable Downlight with flicker free driver, 2 x Black Orbit Wall Light with driver, 6 x White Orbit Wall Light with driver, 4 x Textured Black Onyx Wall Light.
- Beacon Lighting - 5 x Kyber 137cm DC Fan in White, 9 x Eclipse Maxi LED Colour Switch Downlight in White

Electrical - Underground

- A new 2-phase mains supply will be installed and the meter position relocated to a new location on the front boundary. The maximum voltage drop for the new mains cabling has been calculated at 5%. If the client wishes to decrease the maximum voltage drop to 2% additional costs will be incurred.
- Mains cabling and sub-main feeds -

Specifications and Inclusions

Electrical - Underground

- A new 2-phase 63A per phase supply will be installed from the existing power pole on the property and feed a freestanding meter position and main switchboard located on the boundary. 1 x 63A per phase 2-phase supply from the main switchboard to a shed distribution board. 1 x 2-phase 63A per phase supply from the existing shed D/B to the new dwelling D/B. 1 x w/proof gate power supply. 1 x data cable from house to gate.

Security / Intercom / Data

- Provisional Sum allowance, as per Rod Hannah Design Specification.
- Supply and install a Mesh WiFi System.
- Re-installation of existing security camera system.

Cabinetry

- KITCHEN- J01- J03. Substrates and templates fitted, American Oak reeded Polo style farmers doors to hotplate drawers, American Oak veneer finish to farmers doors polo style to island cabinet, 2 pack paint finish to tall cabinet doors as well as fridge overhead doors, allowance for white melamine internal cabinets, Blum Legra Box soft close drawers, handles as per specifications, Allowance for American Oak laminated post to Island, wall oven tower, pantry cabinet with roll out shelves, pull out pantry to 300mm wide tall cabinet, integrated bin, integrated dish washer, overhead cabinets, shadow lines to ceiling.
- BUTLERS PANTRY J.04. Substrates and templates fitted, 2 pack finish to base cabinet doors and appliance doors, white melamine finish to internal cabinets, Blum mechanical push to open drawers, integrated bin, overhead cabinets with farmers Polo style veneer doors, American Oak veneer finish to appliance cabinet internal cabinet, handles as per specifications, 2 x veneer floating shelves, LED lighting channel.
- BUTLERS OPEN SHELIVING. J05. Blossom white laminate finish to open shelf unit, LED light channel fitted.
- LAUNDRY J06. Substrate and template fitted, 2 pack paint finish to base cabinet doors and drawers, 2 pack paint finish to washing machine / dryer tower, Farmers Polo style veneer doors to overhead cabinets, white melamine internal cabinets, push to open drawers, handles as per specifications, LED lighting channel, 2 x hampers, 2 x pull out shelves.
- LAUNDRY LINEN J07. 2 pack paint finish to similar Polo style doors, White melamine internal cabinets, adjustable shelves, shadow lines to ceiling.
- MUD DRYING J08. 2 pack paint finish to similar Polo style doors, white melamine internal cabinets, custom made drying racks, adjustable shelves, handles as per specifications, shadow lines to ceiling.
- MUD SEAT J09. 2 pack paint finish to similar Polo style doors, white melamine internal cabinets, handles as per specifications, open shelf section with American Oak veneer floating shelf and seat, groove detail to back of open section, 3 x hooks. Banquette cushion 1530 x 650 x 100 in Warwick Eastwood Tan.
- POWDERROOM J11. Substrate and template fitted, farmer Polo reeded veneer drawer fronts, Blum Legra Box soft close drawer, LED light channel.
- BED 2 ENSUITE J12. Substrate and template fitted, farmers reeded Polo veneer drawer face, American Oak veneer finish to base cabinet polo style doors, LED lighting channel. Installation of premanufactured framed mirrored shaving cabinet.
- MAIN BATHROOM. J13. Substrate and template fitted, farmers reeded Polo veneer drawer faces, 2 pack paint finish to doors, white melamine internal cabinets, LED lighting channel. Installation of premanufactured framed mirrored shaving cabinet.
- MASTER ENSUITE. Substrate and template fitted, farmers reeded Polo veneer drawer face, American Oak veneer finish, white melamine internal cabinets, Blum Legra box mechanical push to open drawers, led lighting channel. Installation of premanufactured framed mirrored shaving cabinets.
- MASTER ROBE J15- J16. 2 pack paint finish to shaker Polo style doors, white melamine internal cabinets, Blum Legra box mechanical push to open drawers, robe hanging rail cabinets with overhead shelves above, shadow lines to ceiling. Shoe shelves, handles as per specifications.
- BED 2 ROBE J17. 2 pack paint finish to shaker Polo style doors, white melamine finish to internal cabinets, Melamine drawers on soft close ball bearing runners, handles as per specifications and drawings, hanging rails, adjustable shelves, shadow lines to ceiling.
- BED 3 ROBE J18. 2 pack paint finish to shaker Polo style doors, white melamine finish to internal cabinets, Melamine drawers on soft close ball bearing runners, handles as per specifications and drawings, hanging rails, adjustable shelves, shadow lines to ceiling.
- BED 4 ROBE J19. 2 pack paint finish to shaker Polo style doors, white melamine finish to internal cabinets, Melamine drawers on soft close ball bearing runners, handles as per specifications and drawings, hanging rails, adjustable shelves, shadow lines to ceiling.
- LINEN J20. 2 pack paint finish to shaker Polo style doors, white melamine finish to internal cabinets, handles as per specifications and drawings, adjustable shelves, shadow lines to ceiling.
- MPR. J21. Substrate and template fitted, Farmers Polo reeded doors in Natural Oak finish Blum Legra Box soft close drawers, handles TBC.

Specifications and Inclusions

Cabinetry

- STUDY EAST-WEST. J22-23. 2 pack paint finish to shaker Polo style doors, white melamine finish to internal cabinets, Melamine drawers on soft close ball bearing runners, handles to be confirmed, American Oak solid timber bench top, 2 x floating shelves, tall storage cabinets with overheads above, handles to tall cabinets as drawn and specified, shadow lines to ceiling.
- GARAGE SEAT J24. Solid timber American Oak bench top, 2 pack paint finish to up stands. Floating shelf in American Oak solid timber, No allowance for upholstered banquette cushion. Banquette cushion 1200 x 600 x 100 in Warwick Eastwood Tan.
- PAVILLION OUTDOOR KITCHEN. Compact laminate finish doors, Allowance for Stylex waterproof board to internal cabinets.
- POLO STYLE DOORS. All 2 pack Polo style shaker doors are priced on using a 21mm solid MDF door routed to a similar style as farmers doors. All farmers veneer Polo style and Polo reeded doors are as per farmers doors specifications using American Oak veneer with 2 pack clear coat finish.
- HANGING RAILS. Allowance for oval shaped black aluminium hanging rail.
- DRAWERS. Allowance for Blum Legra box soft close drawers, all push to open drawers are priced using mechanical push to open drawers, no allowance for servo drive push to open. Allowance for melamine drawer to robes on soft close ball bearing runners.
- HANDLES. As specified. If no handle has been marked on plans, then there is an allowance for doors or drawers to be push to open. No allowance for servo drive push to open.
- INTERNAL CARCASSES. Allowance for white melamine finish to internal cabinets unless otherwise specified on colour schedule.

Stone Bench Tops

- 20mm Enviro Surfaces Natural - Taj Mahal Honed Block # ES-00150 (Approx 3130mm x 1930mm) - 6 x slabs required.
- Kitchen - 40mm Mitred Edgework. 1 x 4410 x 1100 bench top - Join required. 1 x 1850 x 700 bench top with one standard cooktop cut out 1 x 4490 x 600 bench top with one undermount sink cut out - Join required
- Kitchen - 1 x 1850 x 700 splash back, 2 x 405 x 830 splash back,
- Appliance Cupboard - 40mm Mitred Edgework 1 x 1200 x 600 bench top.
- Pantry - 40mm Mitred Edgework 1 x 4570 x 600 bench top with one undermount sink cut out - Join required.
- Laundry - 40mm Mitred Edgework 1 x 2280 x 650 bench top with one undermount trough cut out.
- Powder - 307mm Mitred Edgework 1 x 1590 x 550 bench top with one integrated basin and three tap holes cut out.
- Powder 1 x 1590 x 150 splash back with two radius corners.
- Master Ensuite - 226mm Mitred Edgework 1 x 1810 x 550 bench top with two integrated basins with six tap holes cut outs.
- Master Ensuite 1 x 890 x 400 shower niche with rear panel.
- 12mm Enviro12 Porcelain - Full Body Range - Calacatta Gold* (Silk)
- MPR - 40mm Mitred Edgework 1 x 3050 x 500 bench top.
- Alfresco - 50mm Mitred Edgework 1 x 4810 x 700 bench top with one standard cooktop cut out - Join required.
- Bathroom - 40mm Mitred Edgework 1 x 2350 x 550 bench top with one undermount basin and three tap hole cut outs.
- Bed2 Ensuite - 40mm Mitred Edgework 1 x 1200 x 550 bench top with one undermount basin and three tap holes cut outs.

Staircase

- Supply and install internal staircase, comprising Pine Strings and MDF Treads and Risers. To be clad in Aged White and Smoked Flooring, as per the remainder of the house.
- Straight flight with 16 risers at 190mm, Going 250mm. Approx width 1100mm. Closed Tread with Housed Stringers.
- 240x32mm stringers. 250x32mm treads. 190x19mm risers.
- Handrails - 45mm dowel rails to inside wall fixed with black brackets.
- Balustrade to comprise 40x6 flat top and bottom rails, 8mm minimum recommended for strength and distortion.
- 6x6 square bar uprights, 12x12 recommended for strength.
- Allowance for standard Dulux range powder coating. Monument - to be confirmed.

Plastering

- Supply and install Plasterboard. Includes: 10mm Ceiling Board, 10mm RE Wall Board, 6mm Villaboard to wet areas, Square set ceiling junctions.
- Keylock style dropped ceilings with lasered battens throughout.
- Revealed window jambs and doors.
- P-50 to internal doors. Allowance for 196 lineal metres.

Specifications and Inclusions

Plastering

- Recessed pelmets included.

Aluminium Window Surrounds

- Supply and installation of 16 x custom 300x8mm Powder coated window surrounds:
- Windows 01, 02 - 2400mm x 1200mm
- Windows 03, 04, 05, 06, 020, 021, 024 - 2400mm x 750mm
- Window 08A - 2100mm x 2510mm
- Window 08B, 09, 010 - 2100mm x 900mm
- Window 018 - 2270mm x 600mm
- Window 022, 023 - 2400mm x 600mm
- Note that the price for the Window Surrounds was not from the preferred supplier, as they were quoting the Sunblade Air, which is 5mm thick at the front and 10mm thick at the back. Should these be reduced to 5mm, it would result in a significant cost saving.

Aluminium Wood Box

- Manufacture of Aluminium Wood Box with 6mm plate construction.
- 400mm high x 2200mm wide x 600mm deep.
- Powder coated Satin Black.

Tiles

- Tile selections as per specification from Rod Hannah Design and Project 5 Interiors.
- Floor tiles to the Master Ensuite are Perini, Pompei Octagon & Dot Bianco Oro Light & Crema Serena Tumbled. Allowance has been made for 108 sheets sized 298mm x 298mm.
- Wall tiles to the Master Ensuite are Lifestiles, Mojito Green laid in a bricked pattern. Allowance has been made for 29m² for 3 walls, as the Eastern/external wall is listed as painted plaster.
- Floor tiles to the main Bathroom and bed 2 Ensuite are Lifestiles, Kemet Crema Marfil Jumbo. Allowance has been made for 18m².
- Wall tiles to the main Bathroom and Bed 2 Ensuite are Lifestiles, Coco Gloss White laid in a bricked pattern. Allowance has been made for 60m².
- Splashback tiles in the Kitchen, Laundry and Butlers are Lifestiles, 100 x 100 Pure White Gradient. Allowance has been made for 7m².
- Epoxy grout to be used to both Ensuities and main Bathroom floors.

Garage Door

- Supply and installation of custom range track Tilt garage door - to suit nominal opening 2400H x 5800W.
- Standard mount behind the opening.
- Galvanised steel frame to be clad in Colorbond Enseam at 6kg per m².
- BAL 40 ember seal to header, and steel weather strips to sides.
- Merlin Commander Elite Tile Door Automatic Opener complete with 2 handsets, 1 wall button, 7 year warranty.

Garage Door - See Specifications

- No allowance has been made to clad the garage door in structural ply, due to it's significant weight. A counterweight door would be required, should structural ply be used with the Enseam cladding.

Driveway

- A Provisional Sum allowance of \$100 per m² (incl GST) has been made for the installation of exposed aggregate concrete driveway, as per the Rod Hanah Design Specification.

Specifications and Inclusions

Paving

- Provisional Sum allowance made for 58m2 of Beauford Crazy Paving (Eco Outdoor) to Porches, as per Rod Hannah Design specification.
- Provisional Sum allowance made for 130m2 of Beauford Crazy Paving (Eco Outdoor) to Pool zone, Alfresco, Terrace and path to West of house, as discussed with Rod Hannah Design.

Plunge Pool - More details are required for fixed cost of all of the items within this category

- Plungie Arena Pool - 3.5m Round, Colour TBC eco Finish Interior Coating, multi-coloured LED light and skimmer box.
- Plungie base preparation - compact the subgrade as per the geotechnical report. Base course material shall be free-draining, strong, durable, washed, open-graded 10-20mm gravel. Install in minimum 75mm thick compacted layers exceeding to at least 200mm beyond the extent of the pool base.
- Plungie standard crane lift from truck to pool location.
- Plungie rock backfill around pool - installation of aggregate around pool shell.
- Installation of pipework, cartridge filter, heater and chlorinator within 5 lineal metres of skimmer box. Allowance has been made for an additional 10 lineal metres, given the proposed location of the pool equipment and distance from the pool.
- Includes standard equipment, including variable speed pump, 150 sp foot cartridge filter, halo 18 gram chlorinator, halo hub with auto acid dosing and ORP probe for chlorine auto adjust output.
- Pool fence comprising 27mm round bar at 100mm centres. 2 x gate sections.
- Includes allowance for waterline mosaic tiles.

General Conditions

- This quote is valid for 30 days.

General Housekeeping

- This tender submission has been prepared in accordance with the tender package provided by Rod Hannah Design, including (but not limited to) the General Specification document, Working Drawings, Engineering Drawings, Interior Plans and associated documents, and Landscape Plan..
- This tender conforms with the information and requirements described in the Rod Hannah Design General Specification document.
- Site access for the duration of the project is to be available to the Builder between 6:30am to 4:30pm during construction.
- Builders will erect mesh signage on temporary fencing with logo. Various Occupational Health & Safety signage will also be erected to temporary fencing for the duration of the project.

Excluded Items

- Boundary Survey, Planning Permit, Building Permit, Appliances, Roof penetrations other than noted in trade breakdown,
- Repairs to pre-existing faults after the installation of RCBOs (safety switches).
- Asbestos Removal (if not listed in quote), Any works associated with materials containing asbestos.
- Costs associated with services such as Electricity, Water etc for the duration of the construction works.
- Please note Quote will change due to change of Plans or Engineering, extra building inspections, unforeseen problems, materials price increase or changes at the request of the Client.
- Blinds, Window furnishings, fencing, landscaping and planting by Owner.
- Selected feature Pendants and Wall Lights, Stair Lights, Kitchen and Laundry appliances, as specified in the Project 5 Interiors Schedule.
- Powder room mirror by Owner.
- Pizza oven, 1050 Jetmaster Open Fireplace Insert, BBQ and appliances to the Alfresco area are not included in this quote.
- Excludes dropped pelmets to living/dining room.

Allowances For Prime Cost Items

Prime Cost Items are a reasonable allowance for items which are yet to be selected or determined

	Description of Prime Cost Item	Quantity	UOM	Allowance incl. GST
4	Earthworks - Site Cut, Footings, Trenching & Spreading of Spoil Onsite			
4.12	Rock for gravel driveway west to East/West of house & lower driveway	6.000	Ea	\$3,960.00
5	Structural Steel - To House, Alfresco and 2 x Chimney Lid			
5.3	Boom lift - if required for Structural Steel Installation	1.000		\$2,200.00
7	Plumbing - Roofing & House Cladding, Gutter Guard, Alfresco Roofing, Septic,			
7.5	Stainless Steel Strip Grate to 3x porch areas (30 LM)	1.000		\$11,935.15
				Allowance including GST: \$18,095.15

Allowances For Provisional Sums

Provisional Sums are a reasonable estimate or allowance for works where the full scope is not yet known

	Description of Provisional Sum Item	Quantity	UOM	Allowance incl. GST
5	Structural Steel - To House, Alfresco and 2 x Chimney Lid			
5.4	Chimney Lid x 2	1.000		\$4,180.00
13	Windows and Glazed Doors - See Specifications			
13.3	Freedom Retractable screens to D3 & D5	1.000		\$6,787.00
19	Security / Intercom / Data - See Specifications			
19.1	Security / Intercom / Data	1.000		\$35,000.00
27	Engineered Timber Flooring and Ceiling Lining - See Specifications			
27.1	Engineered Timber Flooring - Installation - Carpet World	1.000		\$16,324.00
27.2	Engineered Timber Flooring - Aged White and Smoked -straight, Carpet World	331.000	m2	\$40,779.20
27.3	Engineered Timber Lining to Ceiling - Aged White and Smoked -straight, Carpet World	101.000	m2	\$12,443.20
29	Future Glass Mirror Cabinets, Tiling Labour (m2), Internal Crazy Pave,			
29.59	Crazy paving to Powder room, Entry, Laundry and Mudroom floor	26.000	m2	\$14,300.00
34	Landscaping / Planting / Driveway - See Specifications			
34.1	Exposed aggregate concrete driveway	60.000	m2	\$5,999.99
35	Crazy Paving External - See Specifications			
35.1	Crazy paving to Porch x 3 - Screed, Paving & Labour	58.000	m2	\$31,900.00
35.2	Crazy paving to Pool zone, Alfresco, Terrace and path to west of house - screed, paving & labour	130.000	m2	\$71,500.00
36	Plungie Arena Pool - See Specifications			
36.4	Astral eco 18 Heat pump - OPTIONAL	1.000		\$5,610.00
36.5	Pool Fence - Supply & Install Rod's, Concrete, Excavation, Formwork, Labour	1.000		\$24,492.60
				Allowance including GST: \$269,315.99

Quoted Categories		
	Description of category	Total incl. GST
1	Preliminaries Including Builders Warranty Insurance, Construction & Public Liability Insurances & Office Administration	\$159,123.20
2	Location of Services	\$916.01
3	Hire Items - Site Toilet, Temporary Fencing, Bin Hire & Fall Protection	\$49,879.75
4	Earthworks - Site Cut, Footings, Trenching & Spreading of Spoil Onsite	\$33,356.50
5	Structural Steel - To House, Alfresco and 2 x Chimney Lid	\$150,891.44
6	Termite Treatment to perimeter of slab	\$4,252.86
7	Plumbing - Roofing & House Cladding, Gutter Guard, Alfresco Roofing, Septic, Storm Water & Water - See Specifications	\$515,406.35
8	Plumbing Fittings - as per Project 5 Interiors Schedule	\$55,402.26
9	Concrete - Garage Slab, Footings, Screw Piles, Apron to Shed, Internal Fireplace Bench, Pads for Water Tanks and Stairs	\$239,391.47
10	Concrete Polishing - See Specifications	\$11,423.89
11	Frame Materials - Trusses, Floor / Wall / Roof Framing, Concrete Stumps, Doors, Cladding, Arch's & Skirts & Hardware	\$227,881.47
12	Steela Wilbraham Double Doors and all Internal Door Hardware, as per Project 5 Interiors Specification	\$19,435.46
13	Windows and Glazed Doors - See Specifications	\$164,100.09
14	Blockwork and Brickwork to Subfloor, Garage & Driveway Retaining Walls and Alfresco, including, Blocks, Core filling & Waterproofing	\$202,555.47
15	Rendering - See Specifications	\$26,335.17
16	Stone Work to Fireplace Recess - See Specifications	\$12,436.76
17	Electrical - See Specifications	\$118,372.68
18	Electrical - Underground, including Switchboard Setup	\$61,288.61
19	Security / Intercom / Data - See Specifications	\$35,000.00
20	Solar Panels & Battery System - as per Thompson Electrical Solutions quotation provided	\$90,576.51
21	Heating & Cooling - See Specifications	\$98,294.87
22	Cabinetry and Stone Bench Tops - See Specifications	\$360,300.28
23	Staircase, Handrail and Balustrade - See Specifications	\$10,468.65
24	Insulation - as per General Specification and Energy Rating	\$20,088.18
25	Plaster - See Specifications	\$88,760.88
26	Painting - as per General Specification and Project 5 Interiors Schedule	\$49,071.70

Quoted Categories

	Description of category	Total incl. GST
27	Engineered Timber Flooring and Ceiling Lining - See Specifications	\$69,546.40
28	Builders Clean and Window Cleaning	\$5,548.37
29	Future Glass Mirror Cabinets, Tiling Labour (m2), Internal Crazy Pave, Waterproofing, Niche's, Low-Iron Shower Screens, Fluted Glass to Ensuite WC, Shower Base's & Caulking	\$121,079.11
30	Aluminium Window Surrounds and Aluminium Wood Box - See Specifications	\$52,875.13
31	Garage Door	\$7,157.96
32	Carpentry Labour	\$255,172.71
33	Shed Retaining Walls	\$20,867.72
34	Landscaping / Planting / Driveway - See Specifications	\$5,999.99
35	Crazy Paving External - See Specifications	\$103,400.00
36	Plungie Arena Pool - See Specifications	\$100,837.10

Terms and Conditions

Quote Valid for 30 days

"The bitterness of poor-quality is remembered long after the sweetness of a low price has faded from memory." - Aldo Gucci 1938.

The cheapest quote is not always the best, make sure your Builder is registered/licensed and part of the Victorian Building Authority

Quote Total:	\$3,224,995.38
Tax (GST):	\$322,499.62
Total:	\$3,547,495.00