

30.06.2026

Amanda Hagan & Kevin McCoy
188 Balnarring Road
Merricks North VIC 3926

Project: 188 Balnarring Road, Merricks North

Dear Amanda and Kevin,

Thank you for the opportunity to submit this tender.

Please read through the notes carefully and let me know if you have any queries.

If you are trying to reach a certain budget, please share this with us and I can work shop some ideas.

Some of the provisional sums noted can be fixed prior to contract if required. They are noted as provisional sums to show allowances and as a discussion point should value management be required.

Project References:

Our quotation has been prepared based on the following documents:

- Drawings & Design – Rod Hannah Design
- Joinery & Interior Design – Project 5
- Structural Engineering – SJV Consulting Engineers
- Energy Report – SmartStar Energy
- Geotech Report – CivilTest Pty Ltd

Our proposal also refers to & uses the following documents & publications:

- Master Builders Domestic Building Contract
- Domestic Building Insurance provided by BPC
- Applicable Australian Standards

Pricing proposal inclusive of GST: \$3,605,841.00

Provisional Sums – Alfresco Pavillion:

- Concrete plinth and hearth for wood fired pizza oven - \$8,250
- Jetmaster 1050 firebox, supplied and installed - \$10,228.35
- Firewood storage box (if required) - \$1,320
- Porcelain benchtop - \$2,491.50
- Screw piles - \$6,710
- Crazy pavers - \$5,571.31
- Joinery - \$11,924

Provisional Sums – Existing Shed & Pool:

- Plungie pool package inc services - \$66,000
- Supply and install black steel pool fencing - \$24,200
- Excavation and soil spread to existing shed area - \$8,800
- Concrete sleeper retaining walls - \$38,484.60
- Concrete apron works around shed - \$21,329.55

Provisional Sums – Dwelling:

- Screw Piles - \$25,245
- Aluminium windows - \$130,955
- Internal Steela steel doors - \$9,955
- Retractable flyscreens - \$6,787
- Feature front door - \$3,300
- New LPOD dig to Balnarring road (if required) - \$7,964
- Septic system - \$28,023.60
- Ring-main for heat-pump (if required) - \$4,398.90
- Feature lighting supply - \$16,092.82
- Network package/ security/ intercom - \$35,000
- Supply & install 1c Chimenees Phillip Radiante 800 - \$13,235.99
- Ducted heating and cooling system - \$49,215.35
- Hydronic system - \$32,227.56
- Garage door (standing seam) - \$13,442
- Supply & install window shrouds - \$45,480.61
- Internal balustrade and handrail - \$9,555.80
- Baw Baw stone walling supply (sold in 6m2 lots) - \$2,732.40
- Eco Outdoor crazy paving (internal) - \$4,115.85
- Master Ensuite floor tiles (Octagon & Dot Bianco) - \$3,788.99
- Master Ensuite wall tiles (Mojito Green) - \$5,671.37
- Main bathroom and bed 2 ensuite floor tiles (Kemet Crema Marfil Jumbo) - \$10,121.17
- Main bathroom and bed 2 ensuite wall tiles (Coco gloss white) - \$8,912.74
- Kitchen, laundry and butlers splashback (Pure white gradient) - \$973.57
- Joinery package - \$345,059
- Joinery handles - \$6,050
- Stone benchtops - \$45,670.90
- Concrete hearth - \$6,600
- Custom upholstery (Banquet cushion to garage seat & mudroom) - \$1,540
- Suspended stepped landings to entry - \$22,000
- Eco Outdoor crazy paving (external) - \$16,494.07

Exclusions:

- Authority application and contribution fees
- Build permit
- Exposed aggregate concrete driveway (m2 rate in spec insufficient)
- Corten steps and gravel to pavilion – unsure if required in initial tender so assumed to be priced with soft landscape package
- Pool equipment room – Not enough detail shown to price accurately

Client Supply Items:

- Wood-fired pizza oven due to not being shown on FF&E
- Pavillion sink and tap due to not being shown on FF&E
- Items where noted as client supply in Rod Hannah and P5 specification
- Solar package

Notes:

- Blinding concrete if required to meet founding depth for footings to be charged at \$550 p/m3 only if required
- No allowance has been made for repairs or additional works to existing driveway at this stage
- Temp fencing around dwelling during works assumed as not required
- Ducted split systems, allowance for linear slot/bar grills throughout and trenching to locate condenser units off house
- All 15 window shrouds allowed for as per RH floor plan
- Rod Hannah plan has used for pricing of crazy paved areas, including services court steps – COS plan shows some discrepancies and minimal detail - therefore pool and study zones shown on COS plan not yet included
- Joinery based on supply by Farmers doors, not a copy due to timber panels being reeded. Montique and P5 can workshop a cheaper outcome if required to reduce costs
- Square edge express joint villa board allowed to external entry – P5 RCP looks like engineered timber which won't comply
- Pavillion blockwork based on 65m2
- Allowance made for Brodware plug and wastes to match tapware

SITE SPECIFIC INCLUSIONS & TERMS

1. PRELIMINARY SCOPE OF WORKS:

- All works shall comply with the Building Regulations as legislated for and adopted by the State Government, inclusive of any code or other document that is adopted by or specified in the Building Regulations, and any other regulation provided or administered by a state or local authority having jurisdiction over the building works.
- Where in addition to the works referred to in the drawings and specifications, if any authority having jurisdiction over works requires additional work be undertaken to enable the issue of a building approval / permit, or directs that additional work be performed, that work will be at the owner's expense, in accordance with the conditions of the contract.
- Montique Construction Pty Ltd shall supply materials, tools, scaffolding, and do or have works done in all trades necessary to carry out the work indicated on the drawings and in these specifications. This includes a site toilet with monthly cleans, and rubbish removal as required.
- Materials unless otherwise specified, agreed to by the owner and approved of by Montique Construction Pty Ltd and the Local Authority, shall be new, of good quality and in conformity with the drawings and these specifications. Defective materials shall, as soon as practical, be removed from the site.
- Allotment identification – Montique Construction Pty Ltd shall display on site, a conspicuous notice indicating the lot, street or identification number of the property.
- Allotment verification - The Owner shall be responsible for the accuracy and clear delineation of all allotment boundaries.

- Dimensions - Figured dimensions as shown on drawings shall be given preference to scaled dimensions which should only be used where figured dimensions are not indicated.
- Final Completion - Where such work is within the scope of the agreement, Montique Construction Pty Ltd shall remove all builder's equipment and debris from the site, check satisfactory operation of installed equipment, doors, windows, locks, remove paint spots, clean windows, clean floors, clean all plumbing fixtures and fittings, clean cupboards and leave the building and site in a clean and tidy condition. Montique Construction shall obtain and supply owner with all necessary certificates of final approval from the various authorities.

ADMINISTRATIVE PRELIMINARIES:

- Homeowners Warranty Insurance
- Public Liability & Contract All Works Insurance
- Asset protection permit and bond
- Site signage

CONSTRUCTION PRELIMINARIES:

- Site toilet hire
- Skip bins and waste removal
- Construction power
- Scaffold hire / 2-plank
- Miscellaneous excavator hire and/or crane hire
- Generator hire as required
- Water supply throughout duration of build

SITE WORKS & DEMOLITION:

- **Demolition** – Demolition of existing dwelling
- **Excavation** – Detailed excavation and fill as required to reach required level, spread excess soil on-site to owners requirements
- **Termite protection** – Penetration collars (Part A) & perimeter barrier (Part B)
- **Survey set-out** – Establish site hurdles and set out of dwelling by surveyor

FENCING / RETAINING WALLS:

- **190 and 290 core filled blockwork walls** – Included as per structural engineering

STRUCTURAL CONCRETE WORKS & FOUNDATIONS:

- **Screw piles** – Included as per structural engineering
- **Ground floor concrete works** – Supply and install raft slab, strip footings and pad footings as per structural engineering
- **First floor concrete works** – Supply and install perimeter strip footings, pad footings, bondek slab and 150 and 130 suspended slabs as per structural engineering

FRAMING:

- Wall & roof framing as per Australian Standards & Specifications. Allowance for double thickness walls to first floor as per plan

STRUCTURAL STEEL:

- Supplied and installed as per structural engineering drawings

ROOFING, FASCIA & SKYLIGHTS

- **Main roof** – Colorbond 25mm standing seam panels on structural ply substrate (330mm cover)
- **Fascia** – N/A
- **Gutters** – Colorbond 150mm half round as per plan
- **Downpipes** – Installed as per plan
- **Flashings** – Colorbond flashings where applicable
- **Skylights** – Velux VSS M02 double glazed solar opening skylight with remote control and BAL rated flyscreen to ensuite

WINDOWS & GLAZED DOORS:

- **Frames** – By Design Window Solutions
- **Glazing** – As per energy report
- **Hardware** – As supplied by Design Window Solutions
- **Screens** – To all operable windows and flywire door to W17
- **Retractable fly doors** – PS allowance for D3 and D5

PLUMBING (as applicable):

- **Mains supply** – Utilise existing water filter supply
- **Cold water** – 20mm – 15mm UPVC service used throughout
- **Hot water** – 20mm – 15mm UPVC service used throughout
- **Gas** – To cooktop and BBQ
- **Sewer drains** – Underground sewer drains connected to new supplied and installed septic tank
- **Storm water drains** – Utilise existing connection point – PS allowance made to run new outlet down to Balnarring Road if required
- **Water tank** – Supply 4 x 25,000 litre above-ground colorbond steel tanks and 1 x CFA tank
- **Hot water service** – Supply and install new heat pump HWS. PS allowance made for recirculating ring-main system if required

ELECTRICAL:

- **Underground supply** – New 3-phase underground to meter box at front of property near pit, 3-phase sub-mains to existing shed, then to sub-board in house
- **Meter box** – Safety switch with circuit breaker as per Australian standards
- **Smoke detectors** – As per plan
- **Internal lighting** – As per P5 Design
- **External lighting** – As per P5 Design
- **TV** – PS allowance Per Rod Hannah Specification
- **Ceiling exhaust fans** – Wire and fit ducted exhaust fans
- **Power points** – As per P5 Design
- **Downlights** – As per P5 Design
- **Feature sconces and pendant lighting** – As per P5 Design
- **Alarm/CCTV/Intercom** – PS Allowance as per Rod Hannah Design
- **Solar** – No allowance – To be supplied by client
- **Network and WiFi optimisation** – PS Allowance as per Rod Hannah Design
- **Under floor heating** – No allowance – Heated towel rail on Devex thermostat to master ensuite

HEATING/COOLING:

- **System 1** – 12KW ducted split system to serve bedroom wing, MPR and hallway. System configured with a total of 5 linear bar grills. Zoning provided with a standard on/off controller, with each room controlled individually
- **System 2** – 12KW ducted split system to serve the kitchen and dining area. Linear bar grilles installed for supply air outlets, located above the island bench in the kitchen
- **System 3** – 11.2KW VRV system with 3 bulkhead indoor units to serve bedroom 1, study and living area. Bedroom 1 2.8KW, study 2.2KW, living 7.1KW
- **Fireplace** – Supply and install of Cheminees Philippe Radiante 800 free standing fireplace

EXTERNAL CLADDINGS:

- **Cladding** – Supply and installation of colorbond 25mm standing seam panels on structural ply substrate. All flashings concealed fix within cladded areas. All toe moulds, c-channels and windows and doors. Allowed to dress and weather seams over barges on all barge ends to complete zero capping edge
- **Block work and brick work** – Concrete render finish as per specification
- **Garage door** – Clad in colorbond standing seam 25mm panels
- **Window shrouds** – Custom made x 15 windows as per plan

THERMAL INSULATION:

- **Acoustic / Thermal roof & wall bats** - Ceiling and wall insulation replaced throughout
- **Wrap** - Sisalation wrap installed to external side of frame, cavity batten with all required cavity and ridge venting as per code
- **Slab & first floor** – R3.0 foil board to sub-floor as per SmartStar Energy

PLASTER AND FEATURE LININGS:

- **General walling** - Plaster board to walls throughout
- **Ceiling linings** – Plasterboard on laser battens generally throughout
- **Feature linings** – Wild River aged, white, smoked to raked living/dining ceiling as per P5 RCP
- **Wainscoting** – Not applicable
- **Cornice** – Square set plaster junctions throughout
- **Wallpaper** – Not applicable

DOORS:

- **Internal** – Corinthian Moda Primed PMOD 1 generally throughout, Steela Wilbraham matt black double doors to living area
- **Internal and external handles and locks** – As per Project 5 design

FIXINGS:

- **Architraves** – Plastered reveals to all windows and external doors, P50 to all internal timber door jambs
- **Skirting** – 135mm x 19mm hardwood bullnose
- **Bedroom robes** – Custom joinery per P5 design

STAIRCASE AND BALUSTRADE:

- **Stairs** – KDHW Vic Ash with housed stringers
- **Balustrade** – PS allowance made – design to be workshopped as 6x6mm balustrade won't comply

LAUNDRY & MUDROOM:

- **Joinery** – Joinery and stone as per P5 Design

FIXTURES, FITTINGS AND APPLIANCES:

- All items to be supplied as per Project 5 Design where noted to be supplied by Builder

BATHROOM, POWDER & ENSUITES:

- **Vanity units** – Joinery and stone as per P5 Design
- **Shower bases** – Tiled shower bases with tile insert grate or similar
- **Shower screens** – As per Project 5 Design
- **Mirrors** – As per Project 5 Design

KITCHEN & PANTRY:

- **Joinery** – Joinery and stone as per P5 Design
- **Door furniture** – As per Project 5 Design

PAINTWORK:

- **Skirting boards**– 3 coat semi-gloss enamel
- **Plasterboard ceilings** – 3 coat ceiling white
- **Plasterboard walls** - 3 coat low sheen
- **External soffit lining** – 2 coat external low sheen acrylic

WATERPROOFING & CAULKING:

- **External caulking** – Expansion & articulation joints filled with silicon caulk
- **Internal caulking** – Silicon compound caulk applied to all internal corners of tiling, benches, toilets & basins. At builder's discretion
- **Water proofing** – Waterproofed to AS3740-2010

FLOOR & WALL TILES:

- **Floor tiles** – Supplied and installed per Project 5 Design, including internal crazy paving
- **Wall tiles** – Supplied and installed per Project 5 Design

FLOOR COVERINGS:

- **Carpet** – Not applicable
- **Internal flooring** – Supply and install of Wild River aged, white, smoked

FIT OFF:

- **Door hardware** – Supplied and installed as per P5 specifications
- **Joinery handles** – Supplied as installed as per P5 specification
- **Towel rails, WC roll holders, towel hooks/rings** - Supplied and installed per Mendi Moke design
- **Clothesline** – Not applicable – To be advised if required
- **Letterbox and numbers** – Not applicable – To be advised if required

CRAZY PAVING & FEATURE STEPPED LANDINGS:

- **CRAZY PAVING** – 97 m2 Eco outdoor crazy paving laid by stone mason (not tiler or landscaper)
- **Concrete stepped landings** – Provisional sum allowance

SERVICES:

- Any of the services referred to in this section shall be arranged by Montique Construction Pty Ltd for permanent connection to the dwellings. Payment of the associated costs & contributions to the relevant supplier or authority are as below:
- **Sewerage** – New Septic system as per spec. authority fees if applicable by client
- **Storm water** – Connected into existing – Allowance made to run to Balnarrign Road if required
- **Electricity** – New 3 phase underground
- **Water** – Utilise existing water filter – new tanks supplied and installed by builder
- **Telephone** – N/A
- **Gas** – Utilise existing where required

FEES AND CONTRIBUTIONS:

- **Building permit** – Lodgement & payment of required fees & government levies by client
- **Homeowners warranty insurance** – Application & required fees & government levies by builder
- **Build over easement consent** – Any required applications arranged by Rod Hannah Design
- **Asset protection** – Fees paid by builder
- **Adjoining property condition report** – Organised by client if applicable
- **Council development contribution** – Paid by client if applicable

CONTRACT WORKS INSURANCE:

Contract works insurance covers our contractual requirements against loss or damage to the works including items on site to be included in the works. The goods and materials comprising the works will have to be replaced at the builder's expense if they go uninsured.

PUBLIC LIABILITY INSURANCE:

Public liability insurance protects our business against the financial risk of being found liable to a third party for death or injury, loss or damage of property or pure economic loss resulting from our negligence.

ADDITIONAL NOTES:

- Boundary points to be re-established & clearly indicated by others.
- Planning permit conditions that do not form part of the building contract is the owner/developer's responsibility to comply.
- This quote is valid for 60 days

SIGNED:

.....

Joel Dempsey / DBU-42934

Montique Construction

DATE SIGNED:/...../.....