

Construction Cost Estimate

COST PLUS CONTRACT



Prepared for:

Kevin David McCoy & Amanda Nicole Hagan

188 Balnarring Road, Merricks North, VIC, 3926

Date:
Jul 6th, 2026

Reference:

Q-01006

Expiry:
Aug 5th, 2026

Dear Kevin & Amanda,

Thank you for the opportunity to present this **Construction Cost Estimate** for your proposed new residence at **188 Balnarring Road, Merricks North**.

Following our review of the architectural drawings, consultant documentation and project requirements, we are pleased to provide this preliminary Construction Cost Estimate prepared on the basis of a **Cost Plus Building Contract**.

This estimate has been developed to provide a transparent overview of the anticipated construction costs associated with your project. Rather than presenting a fixed lump sum, the estimate has been structured into individual construction stages and trade packages, allowing each component of the works to be clearly understood and reviewed.

As the project progresses through the **Pre-Construction Phase**, subcontractor quotations, supplier pricing, owner selections and consultant documentation will progressively replace the estimated construction costs contained within this document, ensuring the forecast project cost continues to reflect the current project scope.

This proposal includes a detailed Construction Cost Estimate, project specifications, cost summary, project assumptions and the proposed terms and conditions under which Toussaint Building Group Pty Ltd proposes to undertake the Pre-Construction Phase of your project.

The objective of this estimate is to establish a realistic construction budget while providing complete transparency throughout the estimating and pre-construction process. As the project documentation continues to develop, this estimate will be progressively refined to reflect the latest design information, supplier pricing and subcontractor quotations.

Following completion of the Pre-Construction Phase, and should you elect to proceed, a Building Contract will be prepared for your review prior to commencement of construction.

We appreciate the opportunity to be involved in your project and look forward to working with you to deliver a home of exceptional quality.

Should you have any questions regarding this Construction Cost Estimate or wish to discuss any aspect of the proposal, please do not hesitate to contact us.

Kind regards,

Marc Toussaint
Director
Toussaint Building Group Pty Ltd

| COSTINGS

The following **Construction Cost Estimate** has been prepared on a **Cost Plus Contract** basis and provides a transparent breakdown of the anticipated construction costs for the project.

The estimate has been structured by construction stage and trade category to clearly identify the scope and estimated cost of each component of the works. All amounts are shown exclusive of GST and exclude the Builder's Margin at item level.

The values contained within this estimate are based on the project documentation, consultant information and current market pricing available at the time of preparation. As the project progresses, individual trade packages and supplier pricing will be progressively reviewed and refined as construction documentation, selections and subcontractor quotations are finalised.

This estimate is intended to provide a realistic forecast of the anticipated construction cost and forms the basis for ongoing cost planning and financial transparency throughout the project.

1. PRE-CONSTRUCTION PHASE

#	Item	Total (ex.)
1.01	Pre-Construction Services Pre-Construction Phase services including Building Contract preparation, consultant coordination, project documentation review, procurement planning, project programming, client liaison and associated administration prior to commencement of construction.	\$3,450.00

2. PROJECT MANAGEMENT

#	Item	Total (ex.)
2.01	Project Management Project management and coordination throughout the construction period, including programme management, trade coordination, project communications and administration of the construction process.	\$56,000.00
2.02	Contract Administration Contract administration throughout the project, including contract management, correspondence, document control and general administration of the works.	\$26,600.00
2.03	Site Supervision Site supervision throughout the construction period, including trade coordination, site meetings, quality review and day-to-day management of site activities.	\$84,000.00
2.04	General Site Labour General site labour not otherwise allocated to specific trade packages.	\$52,500.00
2.05	Quality, Safety & Compliance Quality assurance inspections, site safety management, SWMS administration, compliance documentation and project quality management throughout construction.	\$6,000.00
2.06	Procurement & Consultant Coordination Trade procurement, supplier coordination, consultant liaison, client meetings and coordination of project information during construction.	\$20,000.00
2.07	Progress Claims, Variations & Project Close-Out Progress claim preparation, variation administration, invoice processing, reconciliations, final inspections, practical completion, handover coordination, defects liability period administration, as-built documentation, manuals and warranties.	\$26,000.00

3. PROJECT INSURANCE

#	Item	Total (ex.)
3.01	Domestic Building Insurance (Owner Warranty Insurance) Domestic Building Insurance / Owner Warranty Insurance based on the estimated construction value. Final premium to be confirmed prior to execution of the Building Contract.	\$30,000.00
3.02	Public Liability Insurance Allocation Project allocation for Public Liability Insurance.	\$3,500.00
3.03	Professional Indemnity Insurance Allocation Project allocation for Professional Indemnity Insurance.	\$2,500.00

4. BUILDING PERMITS & STATUTORY APPROVALS

#	Item	Total (ex.)
4.01	Owner Arranged Building Permit Building Permit to be obtained directly by the Owner through their nominated Building Surveyor. No allowance has been included within this Construction Cost Estimate.	\$0.00
4.02	Additional Building Surveyor Inspections Additional Building Surveyor inspections requested during construction beyond the mandatory inspections included within the Owner's Building Permit.	\$2,500.00
4.03	Asset Protection Permit Asset protection permit including application fee and refundable bond for demolition and construction works.	\$1,350.00

5. PROJECT DOCUMENTATION & OWNER CONSULTANTS

#	Item	Total (ex.)
5.01	Project Documentation, Amendments & Performance Solutions Project documentation amendments, performance solutions, specification updates and associated consultant documentation are to be arranged and paid directly by the Owner. No builder allowance included.	\$0.00

6. SURVEYING

#	Item	Total (ex.)
6.01	Site Surveying Construction surveying required during the works.	\$1,800.00
6.02	Re-establishment Survey Owner provided. No builder allowance included.	\$0.00
6.03	Construction Hurdles & Pegs Labour, materials, hurdles, pegs and survey grids required for construction set-out.	\$3,000.00

7. SITE ESTABLISHMENT

#	Item	Total (ex.)
7.01	Site Security & Protection Site security and protection measures as required during construction.	\$2,000.00
7.02	Temporary Fencing Temporary site fencing for site security, safety and protection of retained vegetation where required.	\$4,200.00
7.03	Site Signage Mandatory project signage and site identification signage.	\$250.00
7.04	Existing Shed - Builder's Site Facilities Owner to provide the Builder with reasonable access to the existing shed for the duration of construction for storage of small tools, project documentation and site management purposes, with active internet/Wi-Fi available for the Builder's use. No separate temporary site office, container or internet allowance has been included.	\$0.00
7.05	Portable Toilet Portable toilet including supply, servicing, hire and removal.	\$2,000.00

8. TEMPORARY SERVICES

#	Item	Total (ex.)
8.01	Temporary Electrical Supply Electricity supply to be paid by the Owner from the existing electrical supply. No builder allowance included. Power to vegetable garden. Owner-supplied feature lights by Owner.	\$0.00
8.02	Temporary Water Supply Temporary construction water from existing tank water and supplementary water supply if required.	\$2,000.00
8.03	Temporary Power Distribution Relocation of existing power meter and temporary power distribution during construction if required.	\$2,500.00

9. WASTE MANAGEMENT

#	Item	Total (ex.)
9.01	Skip Bin Hire Skip bin hire for construction waste at 9 bins @ \$1,200 each. Excludes demolition waste.	\$10,800.00
9.02	Tip Fees Tip runs and disposal outside the demolition scope.	\$2,000.00

10. TEMPORARY ACCESS

#	Item	Total (ex.)
10.01	Rubble Road Base Three truckloads of rubble road base for temporary construction access at \$540 per load.	\$1,620.00
10.02	Bobcat Bobcat hire to place and trim temporary access material.	\$1,200.00

11. DEMOLITION

#	Item	Total (ex.)
11.01	Demolition Contractor Complete demolition package including removal of nominated structures, disposal of materials, tree removal where required and preparation of the site ready for construction.	\$35,000.00

12. EARTHWORKS

#	Item	Total (ex.)
12.01	Bulk Earthworks Bulk earthworks including excavation, spoil relocation/removal, trimming, stockpiling, imported fill if required and ongoing earthworks throughout construction.	\$18,000.00

13. SLEEPER RETAINING WALLS

#	Item	Total (ex.)
13.01	Set Out Retaining Walls Set out of two sleeper retaining walls from existing dwelling/survey control, including retaining walls of approximately 11.2 lm and 34.0 lm with retained heights up to approximately 1.6 m.	\$660.00
13.02	Concrete Post Footings (Auger) Machine hire for boring concrete post footings to the sleeper retaining walls.	\$1,450.00
13.03	Galvanised Steel Posts Galvanised steel posts to concrete sleeper retaining walls. Final post sizes and spacing to be confirmed by supplier/design requirements.	\$5,000.00
13.04	Concrete Sleepers Concrete sleepers to approximately 45.2 lm of retaining walls with retained heights up to approximately 1.6 m. Preliminary measurement based on approximately 58.4 m² of wall face.	\$14,600.00
13.05	Drainage Aggregate Drainage aggregate behind sleeper retaining walls.	\$900.00
13.06	Agricultural Drain Agricultural drainage behind sleeper retaining walls.	\$599.80
13.07	Geotextile Fabric Geotextile fabric behind sleeper retaining walls.	\$500.00
13.08	Backfill & Compaction Backfill and compaction behind sleeper retaining walls using excavator/plant.	\$1,450.00
13.09	Labour & Plant Installation labour and plant for sleeper retaining walls.	\$8,000.00

14. SCREW PILES

#	Item	Total (ex.)
14.01	Screw Pile Contractor Supply and installation of nominated screw piles in accordance with the Structural Engineering drawings and Geotechnical/Soil Report.	\$30,000.00
14.02	Test Pile Installation and testing of one sacrificial test pile if required.	\$2,500.00
14.03	Pile Trimming Return visit to trim screw piles to final levels after installation.	\$2,500.00
14.04	Hot Dip Galvanising to Screw Piles Hot dip galvanising to screw piles if required by final engineering, site conditions or owner direction.	\$5,000.00

15. SEWER

#	Item	Total (ex.)
15.01	Underground Sewer Drainage Underground sewer drainage installed before footings and foundations, including connection point for the septic system.	\$5,000.00

16. FOOTINGS & FOUNDATIONS

#	Item	Total (ex.)
16.01	Complete Footings & Foundations Package Complete footing and foundation subcontract package in accordance with the Structural Engineering drawings and Geotechnical/Soil Report. Includes set out, excavation, strip footings, pad footings, footing beams, masonry retaining wall footings, reinforcement, starter bars, formwork, edge forms, concrete supply, pumping, placement, finishing, curing, garage slab and associated plant/labour/materials.	\$95,000.00

17. COMPACTED GRANULAR FILL

#	Item	Total (ex.)
17.01	Compacted Granular Fill to Infill Footings Complete infill footing package including excavation, reinforcement, concrete, formwork, labour and plant.	\$1,200.00

18. INFILL FOOTINGS

#	Item	Total (ex.)
18.01	Infill Footings to Stairs Complete infill footing package including excavation, reinforcement, concrete, formwork, labour and plant. To be quoted by concrete subcontractor.	\$16,000.00

19. CONCRETE STAIRS

#	Item	Total (ex.)
19.01	Concrete Stairs Complete reinforced concrete stairs including excavation, reinforcement, formwork, concrete, finishing, labour, plant and associated works.	\$28,000.00

20. SITE CLEAN

#	Item	Total (ex.)
20.01	Site Clean Machine hire and site clean following footing and foundation works.	\$2,900.00

21. SEPTIC SYSTEM

#	Item	Total (ex.)
21.01	Septic System Complete septic system by specialist contractor, including system supply, installation and associated connections subject to final septic permit/design requirements.	\$35,000.00

22. CRUSHED ROCK

#	Item	Total (ex.)
22.01	40 mm Crushed Rock Supply and placement of approximately 8 m³ of 40 mm crushed rock beneath footing/slab preparation.	\$960.00

23. STORMWATER

#	Item	Total (ex.)
23.01	Charged 100 mm Stormwater System Charged 100 mm underground stormwater drainage system running back to the rainwater tanks adjacent the existing shed, installed after footings and foundations.	\$9,000.00
23.02	Agi Drains & Site Silt Pits Agricultural drains and site silt pits as required, including filtering/dispersing stormwater to garden areas where required.	\$5,000.00

24. STORMTECH THRESHOLD DRAINAGE

#	Item	Total (ex.)
24.01	Stormtech Threshold Drainage System - Supply Stormtech linear threshold drainage channels, grates, end caps, outlets and accessories to architectural details.	\$25,000.00
24.02	Stormtech Threshold Drainage - Installation Installation, set-out, rebates, falls, connection to the stormwater system and testing of the Stormtech threshold drainage system.	\$10,000.00

25. MASONRY RETAINING WALLS

#	Item	Total (ex.)
25.01	Masonry Retaining Walls / Base Blockwork Package Complete masonry retaining wall/base blockwork package including core-filled blockwork, blocklaying, core filling, N12/N16 reinforcement, scoria backfill, waterproofing/tanking where required, labour, plant and associated materials. Measurement to be confirmed during detailed trade review.	\$80,000.00

26. TERMITE PROTECTION

#	Item	Total (ex.)
26.01	Termite Management System Complete termite management system in accordance with AS 3660.1, project specification and Building Surveyor requirements.	\$5,000.00

27. SUBFLOOR FRAMING

#	Item	Total (ex.)
27.01	Subfloor Framing Carpenter Carpentry labour for subfloor framing, including installation of bearers, joists, yellowtongue flooring and compressed sheet flooring where required.	\$45,000.00
27.02	Bearers, Joists & Yellowtongue Flooring Supply of bearers, joists, blocking, fixings and 19 mm yellowtongue flooring to timber subfloor areas in accordance with architectural and structural drawings.	\$18,000.00
27.03	Compressed Fibre Cement Sheet Flooring Compressed fibre cement sheet flooring where detailed or required for BAL, wet area or external applications.	\$2,000.00

28. SUBFLOOR INSULATION

#	Item	Total (ex.)
28.01	Subfloor Insulation Subfloor insulation in accordance with the Energy Report and NCC energy efficiency requirements.	\$8,000.00

29. UPPER FLOOR WALL FRAMING

#	Item	Total (ex.)
29.01	Upper Floor Wall Frames - Materials Upper floor timber wall framing materials, tie-downs, bracing, lintels and associated fixings.	\$25,000.00

30. ROOF TRUSSES

#	Item	Total (ex.)
30.01	Engineered Roof Trusses - Supply Engineered roof trusses and associated truss design/layout documentation.	\$30,000.00

31. ROOF BEAMS

#	Item	Total (ex.)
31.01	Structural Roof Beams - Supply Structural roof beams and associated connection materials where supplied with the framing package.	\$12,000.00

32. FRAME CARPENTER

#	Item	Total (ex.)
32.01	Frame Carpenter Labour Frame carpenter labour for subfloor coordination, upper floor wall framing, roof trusses, roof beams, bracing, fixings, plant and crane coordination as required.	\$125,000.00

33. EXTERNAL LOCK-UP CARPENTER

#	Item	Total (ex.)
33.01	External Lock-Up Carpenter Labour External lock-up carpentry labour including installation of windows, external doors, steel doors, porch soffit materials, external cladding coordination and associated lock-up carpentry works.	\$8,000.00

34. STRUCTURAL STEEL

#	Item	Total (ex.)
34.01	Structural Steel Supply & Install Structural steel supply and installation including exposed steelwork, lintels, columns, PFCs, plates, bolts, cleats, fabrication, delivery and installation to structural drawings. Exposed steelwork to be protected/finished as required by the project documentation.	\$25,000.00

35. ROOFING

#	Item	Total (ex.)
35.01	Metal Roofing & Roof Plumbing Metal roof sheeting, insulation blanket, flashings, box gutters, sumps, rainheads, gutters, downpipes, fixings and associated roof plumbing to BAL/environment requirements. Roofing materials to be based on the nominated roofing supplier and General Specification.	\$135,000.00

36. SKYLIGHTS

#	Item	Total (ex.)
36.01	Ensuite Skylight Supply of skylight nominated to the ensuite roof area. Installation to be completed by the frame/lock-up carpenter as part of carpentry works.	\$900.00

37. SCAFFOLDING & EDGE PROTECTION

#	Item	Total (ex.)
37.01	Scaffolding & Edge Protection Scaffolding, edge protection and work platforms required for roofing, cladding, glazing and external works.	\$20,000.00

38. CRANAGE & HOISTING

#	Item	Total (ex.)
38.01	Cranage & Material Hoisting Cranage, lifting, material hoisting and glass/steel/roofing handling required throughout construction.	\$8,000.00

39. WINDOWS

#	Item	Total (ex.)
39.01	Window & External Glazing Supply Window and external glazing supply based on Design Window Solutions quote -2618- Ver 4, sub total \$113,550 ex GST. Supply only. Window installation by frame carpenter/builder, not included as a separate window installation allowance. Builder to provide lifting/hoisting equipment, scaffold and work platform for site glazing.	\$113,550.00
39.02	Freedom Retractable Screens to D03 & D05 Option extra from Design Window Solutions quote -2618- Ver 4 for Freedom retractable screens to D03 and D05.	\$6,170.00
39.03	Parkwood TGV Door Option Option extra from Design Window Solutions quote -2618- Ver 4 for Parkwood TGV entry door.	\$5,785.00

40. EXTERNAL DOORS

#	Item	Total (ex.)
40.01	External Doors & Hardware External doors and associated hardware not included in the window package.	\$8,000.00

41. STEEL DOORS

#	Item	Total (ex.)
41.01	Steel Entry Passage Doors - Supply Supply of steel doors to the entry passage. Installation by the frame/lock-up carpenter as part of carpentry works.	\$3,900.00

42. GARAGE DOORS

#	Item	Total (ex.)
42.01	Garage Doors Garage doors, motors, tracks, hardware and installation.	\$15,000.00

43. CHIMNEY BLOCKWORK

#	Item	Total (ex.)
43.01	Chimney Blockwork Above FFL Concrete blockwork chimney construction above finished floor level including reinforcement and associated masonry works.	\$16,000.00

44. WINDOW SHROUDS

#	Item	Total (ex.)
44.01	Window Shrouds Allowance for external window shrouds illustrated on the architectural drawings, including fabrication, installation, fixings, flashings and associated finishing.	\$30,000.00

45. EXTERNAL CLADDING

#	Item	Total (ex.)
45.01	External Cladding - Supply & Install Supply and installation of Colorbond Enseam or equivalent 0.55 mm wall cladding system to external elevations, including flashings, fixings, battens, trims and associated installation requirements.	\$95,000.00

46. SOFFITS & EXTERNAL CEILINGS

#	Item	Total (ex.)
46.01	Porch Soffits & External Ceilings - Materials Supply of soffit/external ceiling lining materials to the porch areas as detailed in the General Specification. No eave lining allowance included as the design has no eaves. Installation by external lock-up carpenter.	\$4,000.00
46.02	Porch Soffits & External Ceilings - Labour Labour allowance for installation of porch soffits and external ceiling linings to the porch areas in accordance with the General Specification.	\$3,800.00

47. RENDERING

#	Item	Total (ex.)
47.01	External Render to Blockwork External render finish to exposed blockwork walls and slab edges as specified, including preparation, beads, movement joints and texture coating where required.	\$18,000.00

48. INSULATION

#	Item	Total (ex.)
48.01	Insulation Package Insulation package in accordance with the General Specification, Energy Report summary, NCC energy efficiency requirements and project specification.	\$22,000.00

49. PLASTER

#	Item	Total (ex.)
49.01	Plasterboard Linings Square-set cornices and square-set window reveals. P50 plaster detail to door openings.	\$95,000.00

50. WATERPROOFING

#	Item	Total (ex.)
50.01	Wet Area Waterproofing Wet area waterproofing/tanking to wet areas, shower recesses, niches and associated wet area preparation to NCC/AS 3740.	\$10,000.00

51. FIX CARPENTRY

#	Item	Total (ex.)
51.01	Internal Fix Carpentry Oak hardwood skirtings and door jambs with clear-coated finish.	\$20,000.00
51.02	Fix Carpentry Materials Fix carpentry materials including oak hardwood skirtings, oak hardwood door jambs, trims, door furniture, internal fix materials and associated hardware as required.	\$32,000.00
51.03	Fix Carpentry Fit-Off Labour Fit-off labour allowance for final fix carpentry adjustment, door hardware fitting, trims and associated completion works.	\$2,800.00

52. FIREPLACE

#	Item	Total (ex.)
52.01	Fireplace & Hearth Package Internal fireplace package and associated hearth/feature works.	\$12,000.00

53. JOINERY

#	Item	Total (ex.)
53.01	Kitchen Joinery Kitchen cabinetry including two-pack/natural oak finishes, melamine internals, hardware and installation to P5ID joinery drawings.	\$38,000.00
53.02	Pantry Joinery Pantry/butler's pantry cabinetry, shelving, hardware and installation to P5ID joinery drawings.	\$18,000.00
53.03	Laundry Joinery Laundry and mudroom cabinetry, benches, shelving and hardware to P5ID joinery drawings.	\$18,000.00
53.04	Bathroom Joinery Bathroom vanities, mirror cabinets, wet area joinery and associated cabinetmaking to P5ID joinery drawings.	\$34,000.00
53.05	Robes, Linen & Storage Joinery Robes, linen and storage joinery including hanging rails, shelves, drawers, doors and hardware to P5ID joinery drawings.	\$30,000.00

54. STONE BENCHTOPS

#	Item	Total (ex.)
54.01	Stone Benchtops & Integrated Stone Items Stone benchtops and integrated stone items including templating, supply and installation to nominated joinery and wet area locations.	\$38,000.00

55. TILING

#	Item	Total (ex.)
55.01	Floor & Wall Tiling Internal floor and wall tiling including wet area wall tiles, floor tiles, splashbacks, trims, grout and tiler labour.	\$50,000.00

56. SHOWER SCREENS & MIRRORS

#	Item	Total (ex.)
56.01	Shower Screens & Mirrors Shower screens, wet area glazing and builder supplied mirrors including associated hardware. Powder room mirror to be supplied by Owner.	\$12,800.00

57. TIMBER FLOORING & TIMBER CEILING LINING

#	Item	Total (ex.)
57.01	Timber Flooring & Raked Timber Ceiling Lining Selected timber flooring to nominated floor areas and matching timber ceiling lining to the large raked Living/Dining ceiling, including battens/fixing system, trims, expansion detailing and installation.	\$42,000.00

58. PAINTING

#	Item	Total (ex.)
58.01	Internal & External Painting Internal and external painting including sealers/undercoats, premium low sheen walls, ceiling flat, semi-gloss doors/woodwork, exterior coatings and caulking.	\$85,000.00

59. ELECTRICAL

#	Item	Total (ex.)
59.01	Electrical Rough-In & Fit-Off Electrical rough-in and fit-off including switchboard, lighting, GPOs, smoke detectors, power to the veggie garden and general electrical works. Feature light fittings are to be supplied by the Owner and installed/connected by the electrician.	\$48,000.00

60. SECURITY / DATA / INTERCOM

#	Item	Total (ex.)
60.01	Security, Data & Intercom Provisions Security, data and intercom allowance as nominated in the General Specification at \$35,000 including GST (\$31,818.18 excluding GST), including data/comms cupboard, data cabling and security/data/intercom provisions.	\$31,818.18

61. SANITARY FIXTURES & FITTINGS

#	Item	Total (ex.)
61.01	Sanitary Fixtures, Fittings & Tapware Sanitary fixtures and fittings including selected basins, baths, toilets, tapware, mixers, wastes and associated wet area fittings not otherwise supplied by the Owner.	\$15,000.00

62. PLUMBING

#	Item	Total (ex.)
62.01	Plumbing Rough-In & Fit-Off Plumbing rough-in and fit-off labour, fixture connections, external taps, LPG gas line connection coordination, water filtration system installation and sanitary plumbing, excluding separate sewer, septic, stormwater, sanitary fixture and water filtration supply allowances.	\$35,000.00

63. LPG GAS SERVICES

#	Item	Total (ex.)
63.01	LPG Gas Bottles, Connections & Gas Lines Two 45 kg LPG gas bottles, gas bottle connections and gas lines to the alfresco barbecue and kitchen cooktop.	\$3,500.00

64. WATER FILTRATION

#	Item	Total (ex.)
64.01	Whole House Water Filtration System - Supply Supply of whole house water filtration system to rainwater tank reticulation serving the residence, likely located in the services recess adjacent the garage external stairs. Installation by plumber under plumbing allowance.	\$5,400.00

65. HOT WATER

#	Item	Total (ex.)
65.01	Heat Pump Hot Water Unit Stiebel Eltron WWK302H 302 L heat pump hot water unit or equivalent, including installation and plumbing/electrical coordination.	\$8,500.00

66. HYDRONIC HEATING

#	Item	Total (ex.)
66.01	Hydronic Heating System Hydronic heating system including panels, manifolds, pipework and installation to final mechanical design.	\$25,000.00

67. SPLIT SYSTEM AIR CONDITIONING

#	Item	Total (ex.)
67.01	Reverse Cycle Split System Air Conditioning Reverse cycle split system air conditioning including units, pipework, drains, electrical coordination and installation.	\$40,000.00

68. APPLIANCES

#	Item	Total (ex.)
68.01	Appliances Owner-supplied kitchen appliances. Allowance for handling and miscellaneous connection materials only. Owner-supplied items are excluded from Builder's insurance for theft, loss or damage.	\$1,000.00

69. SOLAR

#	Item	Total (ex.)
69.01	Solar PV & Battery System Solar PV and battery system based on Thompson Electrical Solutions proposal #5907: 37.13kW PV system, 79 x Jinko 470W panels, 2 x Sigenergy 10kW single phase hybrid inverters, 2 x Sigenergy 48kWh battery stacks, Sigenergy gateway, shed-mounted equipment, underground supplies from house to shed, data/ comms, CT metering and commissioning. Entered exclusive of GST based on quoted total of \$90,576.51 inc GST. Excludes trenching and main switchboard works other than main switches.	\$82,342.28

70. RAINWATER TANKS

#	Item	Total (ex.)
70.01	5 x 10,000L Colorbond Rainwater Tanks Supply and delivery of five 10,000L Colorbond rainwater tanks including lids. One tank fitted with CFA firefighting fittings; four interconnected for domestic rainwater supply.	\$44,000.00

71. DRIVEWAYS

#	Item	Total (ex.)
71.01	Driveway & Vehicle Access Exposed aggregate concrete paving/driveway works to the garage and documented vehicle access / hard surface paving areas. General Specification allowance rate noted at \$100/m²; quantity and final scope to be measured from drawings.	\$30,000.00

72. PAVING

#	Item	Total (ex.)
72.01	Crazy Paving - Supply & Install Total allowance for crazy paving over infill slabs and nominated external paving areas. Final area and scope to be confirmed by measurement from drawings. Concrete/infill slab substrate costed separately.	\$25,000.00

73. ALFRESCO CONSTRUCTION

#	Item	Total (ex.)
73.01	Alfresco Construction Construction of the external alfresco structure including footings, slab, structural framing, roofing, ceilings, external finishes, drainage interfaces and associated building works in accordance with the architectural and structural documentation. Includes associated external works required for completion.	\$120,000.00

74. LANDSCAPING

#	Item	Total (ex.)
74.01	Basic Landscaping Allowance Basic landscaping allowance only. Excludes owner-supplied or undocumented external works unless later confirmed.	\$5,000.00

75. BLINDS / WINDOW FURNISHINGS

#	Item	Total (ex.)
75.01	Window Furnishings Window coverings are to be supplied by the Owner. No builder allowance included.	\$0.00

76. POOL

#	Item	Total (ex.)
76.01	Plunge Pool Plungie / plunge pool allowance including pool shell/system and surrounding safety features as shown on the drawings and requested in the General Specification. Final pool model, equipment, fencing/barrier requirements, certification and connection scope to be confirmed.	\$90,000.00

77. BUILDERS CLEAN

#	Item	Total (ex.)
77.01	Progress Cleaning Progressive builders cleaning during construction.	\$6,000.00
77.02	Window Cleaning Window cleaning at completion.	\$1,500.00
77.03	Final Builders Clean Final builders clean.	\$3,500.00

SPECIFICATIONS

The following Specifications identify the reference documentation, scope clarifications and project exclusions upon which this Construction Cost Estimate has been prepared. They are intended to complement the consultant documentation by recording the assumptions and clarifications specific to this proposal and should be read in conjunction with all referenced project documentation.

1.00 REFERENCES

1.01	Architectural Drawings Rod Hannah Design, project 1837 drawings WD01 to WD12 rev.4 dated 22/5/2026
1.02	Structural Engineering SJV Consulting Engineers project SJV25-8484 sheets S1 to S11 with issue C update and last dated 26/6/2026
1.03	Landscaping Design COS Design job 24015 page HS-01 version 2 dated 14/10/2025
1.04	Joinery Designs Project 5 Interior Design page no.01 to 33 revision R02 dated 14/5/2026
1.05	Electrical & Finishes Designs Project 5 Interior Design page no.01 to 08 revision R04 dated 14/5/2026
1.06	Geotechnical Civil Test repost 121665-1 version 1.0 dated 20/10/2025
1.07	Project Specification Project 5 Interior Design file dated 14/5/2026 14 pages
1.08	General Specification Rod Hannah Design pages 1 to 12 (plus cover page) dated 22/5/2026
1.09	Energy Report SmartStar Energy summary sheet version 2 dated 20/3/26

SUMMARY

The following summary provides an overview of the estimated construction costs, grouped by construction stage and trade category.

The amounts shown represent the current estimated construction cost based on the project documentation and information available at the time of preparation. Category totals are presented exclusive of GST and exclude the Builder's Margin, providing a transparent summary of the anticipated project costs.

This Construction Cost Estimate has been prepared as part of the **Pre-Construction Phase** and is intended to remain a live project cost management document. As the project progresses, individual trade packages will be progressively reviewed and updated to reflect confirmed subcontractor quotations, supplier pricing, owner selections and completed construction documentation.

The objective of this process is to provide ongoing cost transparency and assist informed decision-making throughout the Pre-Construction Phase, prior to entering into a Building Contract.

#	Item	Total (ex.)
1.0	PRE-CONSTRUCTION PHASE	\$3,450.00
2.0	PROJECT MANAGEMENT	\$271,100.00
3.0	PROJECT INSURANCE	\$36,000.00
4.0	BUILDING PERMITS & STATUTORY APPROVALS	\$3,850.00
5.0	PROJECT DOCUMENTATION & OWNER CONSULTANTS	\$0.00
6.0	SURVEYING	\$4,800.00
7.0	SITE ESTABLISHMENT	\$8,450.00
8.0	TEMPORARY SERVICES	\$4,500.00
9.0	WASTE MANAGEMENT	\$12,800.00
10.0	TEMPORARY ACCESS	\$2,820.00
11.0	DEMOLITION	\$35,000.00
12.0	EARTHWORKS	\$18,000.00
13.0	SLEEPER RETAINING WALLS	\$33,159.80
14.0	SCREW PILES	\$40,000.00
15.0	SEWER	\$5,000.00
16.0	FOOTINGS & FOUNDATIONS	\$95,000.00

17.0	COMPACTED GRANULAR FILL	\$1,200.00
18.0	INFILL FOOTINGS	\$16,000.00
19.0	CONCRETE STAIRS	\$28,000.00
20.0	SITE CLEAN	\$2,900.00
21.0	SEPTIC SYSTEM	\$35,000.00
22.0	CRUSHED ROCK	\$960.00
23.0	STORMWATER	\$14,000.00
24.0	STORMTECH THRESHOLD DRAINAGE	\$35,000.00
25.0	MASONRY RETAINING WALLS	\$80,000.00
26.0	TERMITE PROTECTION	\$5,000.00
27.0	SUBFLOOR FRAMING	\$65,000.00
28.0	SUBFLOOR INSULATION	\$8,000.00
29.0	UPPER FLOOR WALL FRAMING	\$25,000.00
30.0	ROOF TRUSSES	\$30,000.00
31.0	ROOF BEAMS	\$12,000.00
32.0	FRAME CARPENTER	\$125,000.00
33.0	EXTERNAL LOCK-UP CARPENTER	\$8,000.00
34.0	STRUCTURAL STEEL	\$25,000.00
35.0	ROOFING	\$135,000.00
36.0	SKYLIGHTS	\$900.00
37.0	SCAFFOLDING & EDGE PROTECTION	\$20,000.00
38.0	CRANAGE & HOISTING	\$8,000.00
39.0	WINDOWS	\$125,505.00
40.0	EXTERNAL DOORS	\$8,000.00
41.0	STEEL DOORS	\$3,900.00
42.0	GARAGE DOORS	\$15,000.00
43.0	CHIMNEY BLOCKWORK	\$16,000.00
44.0	WINDOW SHROUDS	\$30,000.00
45.0	EXTERNAL CLADDING	\$95,000.00

46.0	SOFFITS & EXTERNAL CEILINGS	\$7,800.00
47.0	RENDERING	\$18,000.00
48.0	INSULATION	\$22,000.00
49.0	PLASTER	\$95,000.00
50.0	WATERPROOFING	\$10,000.00
51.0	FIX CARPENTRY	\$54,800.00
52.0	FIREPLACE	\$12,000.00
53.0	JOINERY	\$138,000.00
54.0	STONE BENCHTOPS	\$38,000.00
55.0	TILING	\$50,000.00
56.0	SHOWER SCREENS & MIRRORS	\$12,800.00
57.0	TIMBER FLOORING & TIMBER CEILING LINING	\$42,000.00
58.0	PAINTING	\$85,000.00
59.0	ELECTRICAL	\$48,000.00
60.0	SECURITY / DATA / INTERCOM	\$31,818.18
61.0	SANITARY FIXTURES & FITTINGS	\$15,000.00
62.0	PLUMBING	\$35,000.00
63.0	LPG GAS SERVICES	\$3,500.00
64.0	WATER FILTRATION	\$5,400.00
65.0	HOT WATER	\$8,500.00
66.0	HYDRONIC HEATING	\$25,000.00
67.0	SPLIT SYSTEM AIR CONDITIONING	\$40,000.00
68.0	APPLIANCES	\$1,000.00
69.0	SOLAR	\$82,342.28
70.0	RAINWATER TANKS	\$44,000.00
71.0	DRIVEWAYS	\$30,000.00
72.0	PAVING	\$25,000.00
73.0	ALFRESCO CONSTRUCTION	\$120,000.00
74.0	LANDSCAPING	\$5,000.00

75.0	BLINDS / WINDOW FURNISHINGS	\$0.00
76.0	POOL	\$90,000.00
77.0	BUILDERS CLEAN	\$11,000.00

Sub Total	\$3,166,243.55
GST	\$316,624.36
Total	\$3,482,867.91

| TERMS & CONDITIONS

This Construction Cost Estimate has been prepared by **Toussaint Building Group Pty Ltd** based on the drawings, consultant documentation and information made available at the date of preparation.

This estimate has been prepared for the purpose of establishing the anticipated construction cost of the project and forms part of the **Pre-Construction Phase**. It is not a fixed-price quotation and does not constitute a Building Contract.

The Construction Cost Estimate has been prepared using current supplier pricing, subcontractor rates, industry experience and reasonable construction estimates. Throughout the Pre-Construction Phase, individual trade packages will be progressively reviewed and updated as subcontractor quotations, supplier pricing, owner selections and consultant documentation are finalised.

Unless otherwise noted, this estimate is based on the referenced project documentation and excludes work not reasonably identifiable from that documentation at the time of preparation. Changes to the design, engineering, statutory requirements, authority conditions, owner selections or project documentation may affect the anticipated construction cost.

The Builder's Margin, GST and statutory charges are identified separately where applicable and will be incorporated into the Building Contract.

Upon acceptance of this Construction Cost Estimate, the project will proceed into the **Pre-Construction Phase**, during which Toussaint Building Group Pty Ltd will undertake the agreed pre-construction services, including consultant coordination, project review, contract preparation, procurement planning and associated administration.

Following completion of the Pre-Construction Phase, and should the Owners elect to proceed, a Building Contract will be prepared for review and execution prior to commencement of construction works.

This Construction Cost Estimate should be read in conjunction with the referenced drawings, consultant documentation, project specifications and any subsequent revisions issued during the Pre-Construction Phase.

| QUOTE ACCEPTANCE

Thank you for taking the time to review this **Construction Cost Estimate**.

By signing below, the Owners acknowledge receipt of this Construction Cost Estimate and confirm that they have reviewed the contents of this proposal.

Acceptance of this Construction Cost Estimate confirms that it will form the basis for ongoing project discussions and commencement of the **Pre-Construction Phase**. It is acknowledged that this document is not a fixed-price quotation and does not constitute a Building Contract.

Should the Owners elect to proceed, Toussaint Building Group Pty Ltd will commence the **Pre-Construction Phase**, during which the agreed pre-construction services will be undertaken. These services include preparation of the Building Contract, review of project documentation, consultant coordination, procurement planning, client liaison and associated pre-construction administration.

Upon acceptance, an invoice for the agreed **Pre-Construction Services** will be issued. Payment of this invoice will authorise commencement of the **Pre-Construction Phase**. The cost of these services forms part of the overall project cost and will be incorporated within the subsequent Cost Plus Building Contract.

Following completion of the **Pre-Construction Phase**, and should the Owners elect to proceed with construction, a Building Contract will be prepared for review and execution by both parties prior to the commencement of construction works.

To assist with the preparation of the Building Contract and associated documentation, please review the information below and ensure all Owner details are complete and accurate prior to signing. Any amendments should be noted before execution of this Construction Cost Estimate.

Builder

Builder: Toussaint Building Group Pty Ltd

ABN: 36 666 506 467

Builder Registration: CDB-U 100582

Director: Marc Toussaint

Business Address:
9/33 Milgate Drive
Mornington VIC 3931

Mobile: 0411 723 991

Email: info@toussaintbg.com.au

Owner

Please complete or confirm the following information for inclusion within the Building Contract.

Owner 1: Kevin David McCoy

Mobile: 0404 881 065

Email: zimbirish@gmail.com

Owner 2: Amanda Nicole Hagan

Mobile: 0407 457 712

Email: ahagan123@gmail.com

Project Address:
188 Balnarring Road
Merricks North VIC 3926

Owner Address:
49A Magnolia Road
Gardenvale VIC 3185

The Owners acknowledge that the information provided above is true and correct to the best of their knowledge and authorise Toussaint Building Group Pty Ltd to commence the **Pre-Construction Phase** upon payment of the associated invoice for the agreed **Pre-Construction Services**. The cost of these services will form part of the overall Cost Plus Building Contract should the Owners proceed with the project.

Customer Signature

Full Name

Full Name

Date Signed

Date Signed

Toussaint Building Group Signature

Full Name

Date Signed