



ABN 17139331123

PO Box 18 Toronto, NSW, 2283

Licence no 222593C

Mobile 0406421646

admin@enmoreconstructions.com.au

Thank you for choosing Enmore Constructions Pty Ltd we like to submit you with the following job quotation.

QUOTATION

Date 9/8/2021
Client Mr Phillip Hagan
Address 36 Park ave Caves Beach
Mobile Ben 0448755559
Email bennyclifton@gmail.com
Site address 36 Park ave Caves Beach

SCOPE OF WORKS – INTERNAL AND EXTERNAL RENOVATIONS

1.1 Demolition external

- 1.2 Remove garden area near front door
- 1.3 Remove brick work as on DA plan and roof
- 1.4 Remove windows as per DA plan
- 1.5 Remove garage doors x2

2.1 Demolition internal

- 2.2 remove all floor coverings throughout as per plan
- 2.3 remove all floor and wall tiled surfaces including wet areas
- 2.4 remove all skirting boards and architraves and doors
- 2.5 remove all plaster board walls and ceiling
- 2.6 strip out all wet areas
- 2.7 strip out kitchen
- 2.8 strip all electrical cabling
- 2.9 remove walls as per plan

3.1 New work external

- 3.2 supply and install axon cladding openings (garage, front entrances, rear door)
- 3.3 supply and install concrete slab 150mm thick with 16mm dowel bars chemset into existing slab front court yard
- 3.3 supply and install new windows and doors as per DA plan
- 3.4 supply and install roof tile to front court yard
- 3.5 supply and install roof construction front court yard pitched 140mm x 45mm lvs
- 3.6 supply and install new eaves as required
- 3.7 supply and install new timber stud wall 90mm x35mm
- 3.8 supply and install wall insulation barrier
- 3.9 painting of new work only (1 coat of haymes primer follow by 2 coats of haymes low sheen) to all areas colour TBA

- 4.0 build new shed as per DA plan TBA
- 5.1 **New work internal**
- 5.2 install new walls 90mm x 35mm t2 as per plan
- 5.3 install all new electrical TBA with downlights and new meter box
- 5.4 install all pc items standard
- 5.5 install all wardrobes standard with mirrors to all bed1- bed2 -bed 3 with 1 shelve with hanging rail
- 5.6 waterproof all wet areas with 2 coats under bedding
- 5.7 min 30mm tile bedding throughout all wet areas
- 5.8 tiling throughout all wet areas with smart floor waste
- 5.9 bathroom room and laundry all walls to be tiled floor to ceiling
- 6.0 install all new plaster board walls and ceiling with 90mm cornices
- 6.1 supply and install all new architraves half splad. Fj pine 66 x18 for windows and door frames, fj pine 92x18 all skirting boards
- 6.2 install solid doors to all rooms new arear only
- 6.3 painting complete internal with a 3-coat Haymes system (3 coats low sheen walls ,3 coats ceiling flat 1 coat of primer on all trim follow by 2 coats full or semi-gloss enamel)
- 6.4 supply and install shower screens
- 6.5 install new kitchen and laundry cabinet bench top appliance's and vanities (TBA)
- 6.6 install kitchen tiled splash back 600mm high with 3 cut outs for power
- 6.7 install ducted air con to all living and bedrooms as per DA plan
- 6.8 wall and ceiling batts r 2.5

7.1 **Electrical**

- 36 downlights and switches.
- 1 x weatherproof.
- ESL x 2 pc item
- Strip light x 2 pc item
- 3 x photoelectric smoke alarms.
- 28 x power points standard
- Oven and cooktop circuit x 2.
- exhaust fan x 2

EXCLUSIONS:

Installation & Connection of TV Ariel

Installation & Connection of Telstra Cables at Telstra Street Asset

Allowances	Price including gst
Kitchen joinery	\$ 45,000.00
All Floor and wall tiles (tba)	\$ 5,000.00
New electricals	\$ 9,700.00
Pc items tapes, sinks. Basins. Bath tubes	\$2,000.00
Kitchen appliances	\$3,500.00
Floor covers	\$8,000.00
Laundry joinery	\$8,000.00

OPTION 1 Supply and install of One (1) Reverse Cycle Ducted Air Conditioning system, providing heating and cooling for your home complete with thirteen (13) new ceiling air grilles and one (1) new centrally located return air grille. Continuous Zones Living, Dining & Kitchen 3 ceiling air grilles Zone 1 Bedrooms 1 & 2 2 ceiling air grilles Zone 2 Bedroom 3 1 ceiling air grille Zone 3 Bedrooms 4,5, 6 & 7 4 ceiling air grilles Zone 4 Study 1 ceiling air grille Zone 5 Rumpus 2 ceiling air grilles Capacities: This system would have the capacity to maintain conditioned air throughout economical heating and cooling throughout the continuous zone and any additional (2-3) zones. Electrical Requirements: Single phase metered power is required from the existing supply in the switchboard Supply & Installation of (1) Daikin FDYAN160AV1/RZA160CV1 - Standard Inverter - Single Phase Reverse Cycle Ducted Air Conditioning System Capacity Range (Cool 7.3 kW - 16.3 kW Heat 7.3 kW - 18.2 kW)	\$13,380.00
Supply & Installation of (1) Daikin Cora FTXV71UVMA/RXV71UVMA 7.1 kW Reverse Cycle Split Air Conditioning System	\$3,500.00
Shed/storage	\$20,000

This quote includes all materials and installation (labour).

Total price including gst \$ 228,000.00

All constructions approximately 26 weeks

Allow 21 day for wet days and delays which is not included in 22 weeks of constructions (not including public holidays break)

All workmanship is guaranteed

Construction rubbish (ENMORE CONSTRUCTIONS PTY LTD RUBBISH ONLY) will be removed from site

All working hours 7.00am to 4.00pm

We have all insurance public liability of \$20 million and WorkCover NSW

On behalf of Enmore Constructions Pty Ltd

Roland Karall

Manager Director