



Proposal
Reference: Q1000

Renovation

36 Park Avenue Caves Beach NSW 2281

18 Jul 2021



NEXUS **BUILT**

Integrity In Construction

Dear Benny,

Thank you for the opportunity to provide a quotation for your renovation works.

I have tried to include as much as possible in our quote within the approximate given budget. Things that I haven't included at this stage are the change of roof trusses to allow for higher ceilings, packing up or leveling of the garage floor, and PC items for kitchen, bathroom and laundry, floor coverings. I have tried to detail the quote as much as possible. There are a lot of variables with this type of renovation work so I have tried to be as clear and detailed as possible.

Thanks again for your patience and the opportunity to quote.

Please feel free to call me if you have any questions or matters you would like to discuss as you review the quote. Happy to meet on site and discuss.

This quote is based on the plans and documents provided.

If you would like to proceed with this quote, we will forward you a deposit invoice, which you will need to sign and return to us, so we can proceed with scheduling the works in.

We look forward to hearing from you soon.

Kind Regards,
John Kirton
Nexus Built

Quoted Items

Quoted items represents a break down of the quote for your project. If you have any questions about any item, please feel free to contact us.

Preliminaries

Ref	Description
-----	-------------

1.2	Site Labourer
-----	---------------

1.5	Engineering Fees
-----	------------------

Demolition

Ref	Description
-----	-------------

2.1	Carpenter and labourer to demo as per plans
-----	---

2.2	Labourer to demo brick work and internal component's
-----	--

2.3	Bin Hire mixed waste
-----	----------------------

2.4	Bin bricks only
-----	-----------------

2.5	Removal of garage doors and dispose
-----	-------------------------------------

Termite Protection

Ref	Description
-----	-------------

4.4	Timber frame Perimeter Barrier - Kordon
-----	---

Frame Carpenter

Ref	Description
-----	-------------

- 5.1 Carpentry labour - Frame
- 5.2 Framing timber, hardware, Brace strapping etc.
- 5.3 Frame - 2400 Build on site materials,T2 90 X 45 ,
Timber, Skirt & Arcs

Roof Tiler

Ref	Description
-----	-------------

- | | |
|-----|---|
| 6.1 | Cement Tiles - Battens & Fixing, Insulation |
| 6.2 | Cement roof tiles Supply |
| 6.3 | Sarking Supply & fit |

Windows

Ref	Description
-----	-------------

- | | |
|-----|--|
| 7.1 | External Windows and sliding door install |
| 7.2 | External Windows and Sliding door frame as per plans
and BASIX report |

Electrician

Ref	Description
-----	-------------

- | | |
|-----|----------------------------|
| 8.1 | Electrical as per plans v2 |
|-----|----------------------------|

Plumber

Ref	Description
-----	-------------

- | | |
|-----|---|
| 9.1 | Plumbing rough in and fit off as per plans, hot cold and
sewer rough in and fit off for 2x bathrooms 2x Laundry
2x kitchens HWH |
|-----|---|

Lockup Carpenter

Ref	Description
-----	-------------

- | | |
|------|------------------------------|
| 10.1 | Lock Up Carpentry labour |
| 10.2 | Lock Up hardware |
| 10.3 | Axon cladding and SS fixings |
| 10.4 | Trimming for cladding |
| 10.5 | hardies wall wrap Roll |

Insulation

Ref	Description
-----	-------------

- | | |
|------|---|
| 11.1 | Supply R2.5 Wall batts |
| 11.2 | Fit R2.5 wall batts |
| 11.3 | R2.5 x 580 Insulation Ceiling batts Batts |
| 11.4 | Fit R2.5 Ceiling batts |

Plasterer

Ref	Description
-----	-------------

- | | |
|------|--|
| 12.1 | Supply & fit plasterboard to ceiling's to new bathrooms, new entry. Square set |
| 12.2 | Supply & fit plasterboard to new Bedrooms and bathroom Wet Area Walls |
| 12.3 | Patch & repair existing as required |

Waterproofing

Ref	Description
-----	-------------

- | | |
|------|----------------------------|
| 13.1 | Waterproofing as per plans |
|------|----------------------------|

Tiling

Ref	Description
-----	-------------

- | | |
|------|--|
| 14.1 | Labour to lay Wall Tiles |
| 14.2 | Labour to lay Floor Tiles |
| 14.3 | Cement screed to falls |
| 14.4 | Construct base inc Falls for bathrooms and laundry |
| 14.5 | Feature wall labour |
| 14.7 | Feature tiles |
| 14.8 | Feature wall tile allowance of 10m2 |

Fixing Carpentry

Ref	Description
-----	-------------

- | | |
|-------|---|
| 15.1 | Fixing Carpentry Labour |
| 15.2 | Fixing Hardware |
| 15.3 | Builder's Std Door Jamb x 4 |
| 15.4 | Redicoat 2040 plain Door x 4 |
| 15.5 | Solidcore 2040 front Door allowance \$250 inc gst x 1 |
| 15.6 | Passage Sets PC \$45 Inc gst x 4 |
| 15.7 | Builder's Std Privacy Lock PC \$55 Inc gst x 2 |
| 15.8 | Front door entry Lock set PC \$250 Inc gst |
| 15.9 | Door Stops |
| 15.11 | 67 x 18 pine Architraves |

15.12 67 x 18 pine Skirting

15.13 Bifold door storage room

15.14 Internal Door - Sliding, Cavity Unit, Skirts & Arcs, Pull Latch

Joinery

Ref	Description
-----	-------------

16.1	Kitchens and laundry-see spec list for inclusions
-------------	---

Glazing

Ref	Description
-----	-------------

17.2	Semi-Framed Shower Screen x 2 off
-------------	-----------------------------------

17.5	6mm Mirror Supply & Fit x 2 off
-------------	---------------------------------

Carport

Ref	Description
-----	-------------

18.1	Carport Roofing
-------------	-----------------

18.2	Carport carpentry and materials-Treated pine
-------------	--

Specifications & Inclusions

Electrician

BEDROOM 1/ENSUITE, 3 x GPO 1 x Switch, 5 x DL, 1 x LED strip light, 1 x 1 gang switch, 1 x 2 gang switch, 1 x smoke alarm

BEDROOM 2, 2 x GPO, 1 x 1 gang Switch, 3 x down lights, 1 x smoke alarm

BEDROOM 3, 1 x GPO, 1 x 1 gang Switch, 2 x down light, 1 x smoke alarm

LIVING ROOM/DINING, 6 x down light, 1 x pendant , 1 x 4 gang switch, 4 x GPO, 2 x external spot lights

HALLWAY, 1 x 1 gang switch, 2 x down light.

LAUNDRY 1, 1 x 1 gang switch, 2 x GPO

LAUNDRY 2, 1 x GPO

BATHROOM 1 x 2 gang switch switch, 1 x GPO, 1 x LED strip light, 2 x down light.

KITCHEN 1. 8 x GPO, 3 x down light, Isolation switch for cooktop. New circuit for oven. New circuit for cooktop. * 2 x direction down light. * 1 x 3 gang switch. * 1 x LED strip light. * 1 x external light.

KITCHEN 2/RUMPUS/DINING2. 9 x GPO 9 x down light, Isolation switch for cooktop. * New circuit for oven. * New circuit for cooktop. * 2 x direction down light. * 1 x 1 gang switch. * 1 X 2 gang switch.

HOT WATER 1 x new circuit 1 x isolation switch.

EXCLUSIONS there is no allowance for DIMMERS. there is no allowance for EXTRACTION FANS. there is no allowance for DATA/INTERNET there is no allowance for TV POINT OR AERIAL. there is no allowance for MOTION SENSORS.

There is no allowance for SWITCHBOARD UPGRADES. There is no allowance for MAINS UPGRADES.

Joinery

KITCHEN Doors: Melamine Polytec Aston White - Smooth Doors to Barback and Selected Uppers: Melamine Polytec Woodmatt Panels: as per doors Kickboards: as per doors Bench tops: 40mm Engineered Stone - Caesarstone Midday Splashback: 20mm Engineered Stone

Hinges: Blum soft-close with lifetime warranty Drawers: Blum Antaro Handles: Standard Range - TBC Kitchen height: 2400mm All cabinets and benchtops manufactured and delivered Bulkhead included – raw MDF

Doors: Melamine Polytec Aston White - Smooth Doors to Barback and Selected Uppers: Melamine Polytec Woodmatt Panels: as per doors Kickboards: as per doors Bench tops: 40mm Engineered Stone - Caesarstone Midday

Splashback: 20mm Engineered Stone - Caesarstone Midday Hinges: Blum soft-close with lifetime warranty Drawers: Blum Antaro Handles: Standard Range - TBC Kitchen height: 2400mm All cabinets and benchtops manufactured and delivered Bulkhead included – raw

LAUNDRY 1 Doors: Melamine Polytec Aston White - Smooth Panels: as per doors Kickboards: as per doors Bench tops: 40mm Engineered Stone - Caesarstone Midday Hinges: Blum soft-close with lifetime warranty Handles: Standard Range

LAUNDRY 2 Doors: Melamine Polytec Aston White - Smooth Panels: as per doors Kickboards: as per doors Bench tops: 40mm Engineered Stone - Caesarstone Midday Hinges: Blum soft-close with lifetime warranty Handles: Standard Range

All cabinets and benchtops manufactured and delivered Bulkhead included – raw MDF

BATHROOM Vanity Doors: Mirrored Bench top and Splash: 40mm Engineered Stone - Caesarstone Midday Vanity Hob Wall: Polytec Angora Oak All cabinets and benchtops manufactured and delivered

Plumber

Plumbing rough in and fit off as per plans, hot cold and sewer rough in and fit off for 2x bathrooms 2x Laundry 2x kitchens HWH

This ESTIMATE is subject to a site visit to confirm Heights of sewer to confirm levels and fall requirements Estimate includes all aspects of the scope, including labour materials Includes relocating existing HWH inside to outside as per plans.

All p/c items such as toilets tanks HWH to be supplied by owner. Allowance to remove excess soil from site after ground works is NOT included in this quote. Hitting rock during excavation will incur extra cost.

No gas or stormwater included in this quote.

Preliminaries

Engineering Fees

Tiling

Feature wall tile allowance of 10m²

Quote Summary

Quoted items represents a break down of the quote of your project.If you have any questions about any item, please feel free to contact us.

Sub Total: \$191,136.71

GST: \$19,113.68

Incl. GST: \$210,250.39

Terms & Conditions

This Quote is valid for 30 days

This quotation is valid for 30 days from the date of delivery.
Roof and carport design and structural elements subject to engineers' recommendations.



NEXUS **BUILT**

Integrity In Construction

Contact Details

Nexus Built
+61 416 195 476
john@nexusbuilt.com.au
Newcastle Australia 2290



Powered by Buildxact